


SPACE MART AT VALLEY VISTA

PRELIMINARY/FINAL LAND DEVELOPMENT PLAN

PATTON TOWNSHIP * CENTRE COUNTY * PENNSYLVANIA

FEBRUARY 9, 2024



PennTerra
ENGINEERING, INC.

3075 ENTERPRISE DRIVE
SUITE 100
STATE COLLEGE, PA 16801
PH: 814-231-8285
www.PENNTERRA.com

COPYRIGHT 2024 BY THE ENGINEER
THE INFORMATION CONTAINED HEREON
MAY NOT BE USED OR COPIED IN ANY
MANNER WITHOUT THE WRITTEN
PERMISSION OF THE ENGINEER EXCEPT AS
OTHERWISE PROVIDED BY APPROPRIATE
LAWS OR STATUTES.

© PENNTERRA ENGINEERING 2024
ALL RIGHTS RESERVED

TABLE OF CONTENTS	
SHEET	DESCRIPTION
1	COVER SHEET
2	EXISTING CONDITIONS & DEMOLITION PLAN
3	SIGNATURES & NOTES SHEET
4	RECORD PLAN
5	GEOMETRY AND MATERIALS PLAN
6	GRADING PLAN
7	UTILITY PLAN
8	LANDSCAPING PLAN
9	LIGHTING PLAN - PRE CURFEW
9.1	LIGHTING PLAN - POST CURFEW
9.2	SITE LIGHTING DETAILS
10	FIRST FLOOR PLAN
11	SECOND FLOOR PLAN
12	THIRD FLOOR PLAN
13	BUILDING ELEVATIONS
14	GENERAL SITE DETAILS
15	UTILITY DETAILS
PC1	POST CONSTRUCTION STORMWATER MANAGEMENT PLAN
PC2	POST CONSTRUCTION STORMWATER MANAGEMENT PLAN
PC3	POST CONSTRUCTION STORMWATER MANAGEMENT NOTES & DETAILS
PC4	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS
ES1	EROSION & SEDIMENTATION CONTROL PLAN
ES2	EROSION & SEDIMENTATION CONTROL NARRATIVE
ES3	EROSION & SEDIMENTATION CONTROL DETAILS



BEFORE YOU DIG ANYWHERE IN
PENNSYLVANIA | CALL 1-800-242-1776
NON-MEMBERS MUST BE CONTACTED DIRECTLY

ACT 287 UTILITY INFORMATION: (SERIAL NUMBER: 20231361729)

All utility locations should be verified prior to any construction.
Utility information and locations should be considered approximate.
Contractor shall notify PA One Call prior to any excavation.

SANITARY SEWER
UNIVERSITY AREA JOINT AUTHORITY
1576 SPRING VALLEY ROAD
STATE COLLEGE, PA 16801
PHONE: (814) 238-5361

PUBLIC WATER
STATE COLLEGE BOROUGH WATER AUTHORITY
1201 WEST BRANCH ROAD
STATE COLLEGE, PA 16801
PHONE: (814) 238-6766

NATURAL GAS
COLUMBIA GAS OF PENNSYLVANIA
2550 CAROLEAN INDUSTRIAL DRIVE
STATE COLLEGE, PA 16801
PHONE: (814) 278-5840


ELECTRIC
ALLEGHENY POWER COMPANY
2800 EAST COLLEGE AVENUE
STATE COLLEGE, PA 16801
PHONE: (814) 237-5721

TELEPHONE
VERIZON
224 SOUTH ALLEN STREET
STATE COLLEGE, PA 16801
PHONE: (814) 231-6511

CABLE TELEVISION
COMCAST
1155 BENNER PIKE
STATE COLLEGE, PA 16801
PHONE: (814) 238-5050

STORM SEWER
PATTON TOWNSHIP
100 PATTON PLAZA
STATE COLLEGE, PA 16803
PHONE: (814) 234-0271





Designer(s)	MJA
Environmental	MSF
Proj. Manager	CAF
Surveyor	MAX
Perimeter Ck.	
Book	Pg.
File	22296-FINAL-02-ELCON & DEM.
Layout	EX. COND. PLAN

Date	Description
	REVISIONS

SPACE MART AT VALLEY VISTA

PATTON TOWNSHIP
 CENTRE COUNTY
 PENNSYLVANIA

**PRELIMINARY/FINAL
 LAND DEVELOPMENT
 PLAN**

**EXISTING
 CONDITIONS &
 DEMOLITION PLAN**

PROJECT NO.	22296
DATE	FEBRUARY 9, 2024
SCALE	1" = 50'
SHEET NO.	2

EXISTING LINE TABLE

LINE	DIRECTION	LENGTH
L1	S 12° 02' 26" E	23.00'

EXISTING CURVE TABLE

CURVE	LENGTH	RADIUS	TANGENT	CHORD DIRECTION	CHORD	DELTA
C1	569.58'	1065.92'	291.76'	N 44° 18' 44" W	562.82'	30° 36' 58"
C2	63.35'	342.50'	31.77'	N 86° 56' 05" E	63.26'	10° 35' 52"
C3	110.06'	1050.42'	55.08'	S 55° 22' 32" E	110.01'	6° 00' 12"


SURVEY FEATURES LEGEND

- Property Line, Lot Line or Right of Way Line
- Adjoining Property Line
- Building Setback Line
- Easement Line
- Property Corner Found
- Project Benchmark

EXISTING FEATURES LEGEND


- Existing Building
- Existing Curbing & Edge of Pavement
- Existing Concrete Areas
- Existing Bituminous Areas
- Existing Gravel Areas
- Existing Contours w/ Elevation (1's & 2's)
- Existing Contours w/ Elevation (5's & 10's)
- Existing Sanitary Sewer w/ Manhole
- Existing Water Line w/ Valve
- Existing Storm Sewer Line w/ Inlet
- Existing Gas Line
- Existing Overhead Utility Line w/ Pole
- Existing Fire Hydrant
- Existing Manhole
- Existing Utility Pole
- Existing Guy Wire
- Existing Storm Sewer Inlet Type-M
- Existing Storm Sewer Inlet Type-C
- Existing Utility Main Valve
- Existing Utility Meter
- Existing Bollard
- Existing Clean-Out
- Existing Handicap Symbol
- Existing Sign
- Existing Soil Limit Line / Boundary
- Existing Soil Type
- Existing Deciduous Tree
- Existing Evergreen Tree
- 25% or Greater Slopes

SOILS LEGEND
 Soil cover on the site consists of:
 MrB - Morrison sandy loam, 2%-8% Slopes
 MrC - Morrison sandy loam, 8%-15% Slopes
 URB - Urban land - Hagerstown complex, gently sloping




GENERAL SITE DEMOLITION NOTES:

- The Contractor is responsible for obtaining all local and state permits required for demolition work unless other arrangements are coordinated with the owner.
- The Contractor shall indemnify and hold harmless the Owner and/or architect and engineer for any and all injuries and/or damages to personnel, equipment and/or existing facilities in the demolition and construction described in the plans and specifications.
- Existing conditions as depicted on these plans are general and illustrative in nature and do not include mechanical, electrical and miscellaneous structures. It is the responsibility of the Contractor to examine the site and be familiar with existing conditions prior to bidding on the demolition work for this project. If conditions encountered during examination are significantly different than those shown, the Contractor shall notify the architect and engineer immediately.
- All existing utilities not to be removed or abandoned are to remain operational at all times. Appropriate existing utilities shall remain in service until replacement/relocated utilities are operational.
- Existing above and below ground structures within the limits of new construction noted to be removed shall be razed unless noted otherwise in this construction set, architectural plans and/or project specifications. This includes foundation slabs, walls, and footings.
- Before excavation, all underground utilities shall be located in the field by the proper authorities. The Contractor shall notify PA One Call 1-800-242-1776. The location of all utilities and underground structures are approximate and may not all be shown. It is the responsibility of the Contractor to determine the existence and exact location of all utilities and underground structures.
- All demolition waste and construction debris shall be removed by the Contractor and disposed of in a state approved waste site and in accordance with all local and state codes and permit requirements.
- All utility removal, relocation, cutting, capping and/or abandonment shall be coordinated with the appropriate utility company.
- The burning of cleared material and debris shall not be allowed without approval from the owner and appropriate governing agency.
- Erosion and sedimentation control measures around areas of demolition shall be installed prior to initiation of demolition activities. Refer to plan and details for site specific information including tree protection details, if necessary.
- Asbestos or hazardous materials, if found on site, shall be removed by a licensed hazardous materials Contractor. Contractor shall notify Owner immediately if hazardous materials are encountered.
- Contractor shall protect all corner pins, monuments, property corners, and benchmarks during demolition activities. If disturbed, the Contractor shall have disturbed items reset by a licensed surveyor at the Owner's expense.
- Contractor shall adhere to all local, state, federal, and OSHA regulations operating demolition equipment around utilities.
- Contractor shall provide and maintain traffic control measures in accordance with the PennDOT standards, and as required by local agencies working in and/or along streets, roads, highways, etc. It shall be the Contractor's responsibility to obtain approval and coordinate with local and/or state agencies regarding the need, extent, and limitations associated with installing and maintaining traffic control measures.
- Contractor shall protect at all times adjacent structures and items from damage due to demolition activities.
- Contractor shall coordinate existing facilities utility disconnects with the Owner prior to anticipated demolition of structures.
- Contractor shall refer to Construction Plans for other pertinent information where applicable.
- Contractor shall replace or repair to the Owner's satisfaction all curb, utilities, sidewalks, landscaping, etc. damaged during construction that are not indicated to be removed.
- Contractor shall be responsible for all costs and work required to adjust existing and proposed utilities and appurtenances to finish grades within the limit of work.
- All paving to be removed shall be sawcut to provide a sharp clean edge. All sidewalks to be removed shall be sawcut at the nearest joint. Existing pavement shall be removed as required for new curb, walkway, or utility construction.
- Contractor shall verify the location of manholes, inlets, valves, etc. Contractor shall test pit existing utilities as deemed necessary within the limits of construction to determine the exact location and depth as required. Report any discrepancies from that indicated on the plan to the architect and engineer. All existing utilities shall be retained unless marked otherwise, and appurtenances shall be adjusted to final grade. Damage to existing conditions and utilities to remain shall be repaired as required to the Owner's satisfaction at the expense of the Contractor.
- Contractor shall coordinate with utilities companies on installation, relocation or replacement of electrical, phone, gas and cable services.



GRADING NOTES:

- The project benchmark is Existing Manhole HD-6 in the Home Depot Parking Lot. Elev. = 1324.87.
- All existing trees, vegetation, pavements, concrete foundations, structures and organic topsoil shall be stripped and removed from new construction areas unless noted otherwise.
- All areas not paved shall be sodded, topsoiled, seeded, mulched or landscaped unless otherwise noted in the construction drawings, site specifications or instructed by the Owner.
- Contractor shall refer to the geotechnical report prior to initiation of any earthwork activity.
- The maximum slope within all the handicapped parking spaces shall be 2.00% in any direction.
- The maximum slope for all on-site sidewalks shall be 4.90% with a maximum cross slope of 2.00% and curb ramps shall have a maximum slope of 6.30%.
- Proposed spot elevations are to the bottom of the curb unless noted otherwise.
- The Contractor shall notify the assigned inspection agency before any retaining wall construction. Retaining walls shall be constructed per the project specification approved building permit and certified by the assigned inspection agency.
- All fill material brought on to the job by the Contractor must comply with all applicable D.E.P. regulations regarding clean fill.
- All areas disturbed during construction, not designated to receive paving or mulch, shall be fine graded, topsoiled, & seeded unless otherwise noted in the construction drawings, site specifications or instructed by the Owner.
- The Contractor shall notify the Owner's testing agency before any placement and compaction of fills on the site. Fill areas shall be prepared and compacted per the project specifications and certified by the Owner's testing agency. Contractor shall be responsible for removal, retesting, and replacement of fills not meeting the specifications. The Contractor is also responsible for all expenses associated with replacement of fills not meeting the specifications.
- The Contractor shall notify the assigned inspection agency before any retaining wall construction. Retaining walls shall be constructed per the project specification approved building permit and certified by the assigned inspection agency.
- The Contractor shall stake out and protect all areas designated not to be disturbed, such as wetlands, environmentally sensitive area, etc.



EXISTING FEATURES LEGEND

- Existing Building
- Existing Curbing & Edge of Pavement
- Existing Concrete Areas
- Existing Bituminous Areas
- Existing Gravel Areas
- Existing Contours w/ Elevation (1's & 2's)
- Existing Contours w/ Elevation (5's & 10's)
- Existing Sanitary Sewer w/ Manhole
- Existing Water Line w/ Valve
- Existing Storm Sewer Line w/ Inlet
- Existing Gas Line
- Existing Overhead Utility Line w/ Pole
- Existing Fire Hydrant
- Existing Manhole
- Existing Utility Pole
- Existing Guy Wire
- Existing Storm Sewer Inlet Type-M
- Existing Storm Sewer Inlet Type-C
- Existing Utility Main Valve
- Existing Utility Meter
- Existing Bollard
- Existing Clean-Out
- Existing Handicap Symbol
- Existing Sign
- Existing Soil Limit Line / Boundary
- Existing Soil Type

SURVEY FEATURES LEGEND

- Property Line, Lot Line or Right of Way Line
- Adjoining Property Line
- Building Setback Line
- Easement Line
- Property Corner Found
- Project Benchmark

PROPOSED FEATURES LEGEND

- PROPOSED BUILDING
- PROPOSED CURBING & EDGE OF PAVEMENT
- PROPOSED CONCRETE AREAS
- PROPOSED BITUMINOUS PAVEMENT AREAS
- PROPOSED RETAINING WALL
- PROPOSED CHAINLINK FENCE
- PROPOSED MINOR CONTOURS W/ ELEVATION (1's & 2's)
- PROPOSED MAJOR CONTOURS W/ ELEVATION (5's & 10's)
- PROPOSED SPOT ELEVATION
- PROPOSED GRADE SLOPE
- PROPOSED 6" PVC SANITARY SEWER LATERAL W/ CLEAN OUT
- PROPOSED 8" WATER LINE W/ VALVE
- PROPOSED STORM SEWER W/ TYPE C INLET
- PROPOSED STORM SEWER ROOF DRAIN
- PROPOSED STORM SEWER INLET - TYPE M
- PROPOSED PAINTED HANDICAPPED PARKING SYMBOLS
- PROPOSED TRAFFIC FLOW ARROWS (NOT PAINTED)

PennTerra ENGINEERING INC.
 3075 ENTERPRISE DRIVE
 SUITE 100
 STATE COLLEGE, PA 16801
 PH: 814-231-8285
 www.PENNTERRA.com

COPYRIGHT 2024 BY THE ENGINEER
 THE INFORMATION CONTAINED HEREIN MAY NOT BE USED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER UNLESS OTHERWISE PROVIDED BY APPROPRIATE LAWS OR STATUTES.
 © PENNTERRA ENGINEERING 2024
 ALL RIGHTS RESERVED

C. ANTHONY FRUCHTL
 ENGINEER
 PE-062413
 PENNSYLVANIA

Designer(s)	MJA
Environmental	MSF
Proj. Manager	CAF
Surveyor	MAX
Perimeter Ck.	
Book	Pg.
File	22296-FINAL-06-GRADING
Layout	GRADING PLAN


Date	Description
	REVISIONS


SPACE MART AT VALLEY VISTA
 PATTON TOWNSHIP
 CENTRE COUNTY
 PENNSYLVANIA

PRELIMINARY/FINAL LAND DEVELOPMENT PLAN

GRADING & STORMWATER MANAGEMENT PLAN

PROJECT NO.	22296
DATE	FEBRUARY 9, 2024
SCALE	SHEET NO.
1" = 30'	6





Designer(s)	MJA
Environmental	MSF
Proj. Manager	CAF
Surveyor	MAX
Perimeter Ck.	
Book	Pg.
File	22296-FINAL-07-UTILITIES
Layout	UTILITY PLAN

Date	Description
	REVISIONS


SPACE MART AT VALLEY VISTA

PATTON TOWNSHIP
 CENTRE COUNTY
 PENNSYLVANIA

PRELIMINARY/FINAL LAND DEVELOPMENT PLAN

UTILITY PLAN

PROJECT NO.	22296
DATE	FEBRUARY 9, 2024
SCALE	1" = 30'
SHEET NO.	7



WATERLINE CONNECTION DETAIL
 1" = 30'

PROPOSED FEATURES LEGEND

- PROPOSED BUILDING
- PROPOSED CURBING & EDGE OF PAVEMENT
- PROPOSED CONCRETE AREAS
- PROPOSED BITUMINOUS PAVEMENT AREAS
- PROPOSED RETAINING WALL
- PROPOSED CHAINLINK FENCE
- PROPOSED MINOR CONTOURS W/ ELEVATION (1's & 2's)
- PROPOSED MAJOR CONTOURS W/ ELEVATION (5's & 10's)
- PROPOSED 6" PVC SANITARY SEWER LATERAL W/ CLEAN OUT
- PROPOSED 8" WATER LINE W/ VALVE
- PROPOSED STORM SEWER W/ TYPE C INLET
- PROPOSED STORM SEWER ROOF DRAIN
- PROPOSED STORM SEWER INLET - TYPE M
- PROPOSED PAINTED HANDICAPPED PARKING SYMBOLS
- PROPOSED TRAFFIC FLOW ARROWS (NOT PAINTED)

EXISTING FEATURES LEGEND

- Existing Building
- Existing Curbing & Edge of Pavement
- Existing Concrete Areas
- Existing Bituminous Areas
- Existing Gravel Areas
- Existing Contours w/ Elevation (1's & 2's)
- Existing Contours w/ Elevation (5's & 10's)
- Existing Sanitary Sewer w/ Manhole
- Existing Water Line w/ Valve
- Existing Storm Sewer Line w/ Inlet
- Existing Gas Line
- Existing Overhead Utility Line w/ Pole
- Existing Fire Hydrant
- Existing Manhole
- Existing Utility Pole
- Existing Guy Wire
- Existing Storm Sewer Inlet Type-M
- Existing Storm Sewer Inlet Type-C
- Existing Utility Main Valve
- Existing Utility Meter
- Existing Bollard
- Existing Clean-Out
- Existing Handicap Symbol
- Existing Sign

SURVEY FEATURES LEGEND

- Property Line, Lot Line or Right of Way Line
- Adjoining Property Line
- Building Setback Line
- Easement Line
- Property Corner Found
- Project Benchmark

STATE COLLEGE BOROUGH WATER AUTHORITY:

All private water main & lateral service construction shall be in accordance with State College Borough Water Authority's (SCBWA) material & installation specifications for "private" distribution lines, service lines & fire hydrants", latest edition



All water line pipes shall meet the State College Borough Water Authority's "public water main, service connections & fire hydrant specifications for Contractor installation" as well as "material & installation specifications for "private" distribution lines, service lines & fire hydrants", latest edition.

UNIVERSITY AREA JOINT AUTHORITY:

Sanitary sewer laterals & clean-outs beyond UAJA's utility easement shall be PVC schedule 40 in accordance with UAJA specifications. Sanitary sewer laterals within the utility easement shall be PVC SDR-35.

Contractor shall coordinate depths of non-gravity utility lines, gravity line inverts & other non-gravity lines to obtain adequate depths, clearances, & coverage.

The Contractor shall refer to the architectural plans for the exact location of utility entrances, building dimensions, roof leaders exit doors, exit ramps, and porches. All site work shall be done in accordance with the plans prepared by PennTerra Engineering, the current regulations of the governing municipality, and all other pertinent federal, state & local laws. Any conflicts between the architectural plans and site plans shall be reported immediately to the Owner's representative



UTILITY NOTES:

- Before excavation, all underground utilities shall be located in the field by the proper authorities. The Contractor shall notify PA One call at 1-800-242-1776. The location of all utilities and underground structures are approximate and may not all be shown. It is the responsibility of the Contractor to determine the existence and exact location of all utilities and underground structures.
- It is the responsibility of the Contractor to bid and perform all utility work in compliance to all applicable local and state codes and regulations. The Contractor shall be responsible for all fees associated with the installation, testing and final acceptance of all proposed utilities construction unless other arrangements have been made with the owner.
- Contractor shall be responsible for all fees associated with the installation, inspection, testing and final acceptance of all proposed utility construction.
- Contractor shall coordinate with the appropriate utility company on the addition, removal and/or relocation of utilities and utility poles and the extension of all proposed utilities to the proposed facilities.
- All utilities shall be installed in accordance with the specifications of the respective utility company. It is the responsibility of the Contractor to ensure all utilities are installed correctly to meet project requirements whether performed by the Contractor or not.
- Contractor shall verify all utility service connections at the proposed building with the architectural/mechanical/plumbing/electrical plans.
- An as-built drawing of new utility services shall be prepared by the Contractor and submitted to the Owner upon completion of the project.
- All sanitary sewer & water lines shall have 48" minimum coverage.
- All public water main construction and all private water main & lateral service construction shall be in accordance with the water authority's standards and specifications.
- All sanitary sewer service laterals shall be in accordance with the sanitary sewer authority's standards and specifications. PVC pipe material shall be as shown on plan.
- An as-built drawing of new utility services must be prepared by the Contractor and submitted to the Owner upon completion of the project.
- The Contractor shall be responsible for all costs and work required to adjust existing and proposed utilities and appurtenances to finished grades within the limits of work.
- The Contractor shall be responsible for coordination with utility companies on location/removal and/or replacement of electrical, phone, gas, sanitary, water, and cable services.

PLANTING SCHEDULE					
SYMBOL	KEY	QTY	COMMON NAME	BOTANICAL NAME	SIZE
STREET TREES					
WO	26	WHITE OAK	Quercus alba	2-1/2" CAL.	
PARKING LOT / BUFFER YARD CANOPY TREES					
WO	11	WHITE OAK	Quercus alba	2-1/2" CAL.	
GL	4	GREENSPIRE LINDEN	Tilia cordata 'Greenspire'	2-1/2" CAL.	
SL	11	AMERICAN HORNBREAM	Coprinus caroliniana	4" CAL.	
UNDERSTORY / EVERGREEN TREES					
DW	9	DOGWOOD	Cornus alternifolia	1 1/2" CAL.	
ER	11	EASTERN REDBUD	Cercis canadensis	3" CAL.	
PD	21	WHITE PINE	Cornus alternifolia	8' MS	
H	14	HEMLOCK	Tsuga canadensis	6' MS	
SHRUBS					
Y	42	DENSIFORMIS YEW	Taxus media 'Densiformis'	24" HT.	
BV	32	BURKWOODII VIBURNUM	Viburnum x burkwoodii	24"-30" HT.	

NOTES: ALL TREES AND SHRUBS SHALL BE PLANTED IN ACCORDANCE WITH THE PATTON TOWNSHIP STANDARDS. STREET TREES SHALL BE ONE OF THE SPECIES LISTED. A SINGLE SPECIES SHALL ONLY COMPOSE A TOTAL OF 20% OF THE TOTAL STREET TREES.

- LANDSCAPE NOTES:**
- THE MULCH IS TO BE DOUBLE SHREDDED HARDWOOD BARK MULCH, WELL AGED AND DARK IN COLOR. APPLY THE MULCH 4" THICK. PLANT MATERIAL SUBSTITUTIONS MAY ONLY BE PERMITTED AT THE APPROVAL OF THE OWNER, TOWNSHIP AND ENGINEER OR LANDSCAPE ARCHITECT.
 - ANY PLANTINGS WHICH DO NOT SURVIVE FOR A PERIOD OF ONE YEAR FROM THE DATE OF PLANTING ARE TO BE REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
 - ALL NEW PLANT MATERIAL IS TO BE KEPT WATERED BY THE LANDSCAPE CONTRACTOR WHEN WORKING ON SITE UNTIL COMPLETION OF THE LANDSCAPE OR SEASON'S END (THEN RESUME NEXT SEASON UNTIL PROJECT IS COMPLETED). THE OWNER WILL BE RESPONSIBLE FOR WATERING THEREAFTER.
 - ALL DISTURBED AREAS NOT BEING PLANTED IN TREES OR SHRUBS ARE TO BE FINE GRADED AND SEEDING WITH A HARDY PERENNIAL GRASS SEED MIXTURE AND MULCHED WITH STRAW.
 - ALL CALLIPER MEASUREMENTS FOR LANDSCAPING SHALL BE MEASURED AT 6" ABOVE THE ROOT BALL.
 - ALL LANDSCAPED ISLANDS SHALL BE EXCAVATED TO A MINIMUM DEPTH OF 2" AND FILLED WITH SUITABLE MATERIAL.
 - ALL ABOVEGROUND UTILITY BOXES WILL BE SCREENED PER SECTION 175-40.4.C(2) OF THE TOWNSHIP ZONING ORDINANCE.
 - AN UNOBSTRUCTED 24" OVERHANG AREA SHALL BE PROVIDED ALONG ALL PERIMETER PARKING STALLS. ALL PLANTINGS SHALL BE LOCATED OUTSIDE OF THIS OVERHANG AREA.

BUFFER YARD CALCULATIONS:


1. BUFFER YARD 'B' = 565 LF @ 15' WIDE	REQUIRED:	PROPOSED:
2.0 CANOPY TREES / 100 LF	= 11 CANOPY TREES	23
4.0 UNDERSTORY TREES / 100 LF	= 23 UNDERSTORY TREES	34
6.0 SHRUBS / 100 LF	= 34 SHRUBS	

I-99 INTERCHANGE BUFFER YARD CALCULATIONS (FOR SETBACK REDUCTION):


REQUIRED:	PROPOSED:
4.0 CANOPY TREES (4" CALIPER) / 100 L.F. X 352 L.F. X 75% = 11 TREES	11 TREES
4.0 UNDERSTORY TREES (3" CALIPER) / 100 L.F. X 352 L.F. X 75% = 11 TREES	11 TREES
16.0 SHRUBS / 100 L.F. X 352 L.F. X 75% = 42 SHRUBS	42 SHRUBS
8.0 EVERGREEN TREES / 100 L.F. X 352 L.F. X 75% = 21 TREES	21 TREES

STREET TREES:


REQUIRED:	PROPOSED:
1 CANOPY TREE / 40 L.F. X 1,042 = 26 TREES	26 STREET TREES




SHRUB PLANTING
NO SCALE




TREE PLANTING
NO SCALE



TYPICAL DECIDUOUS TREE PLANTING (ON-SLOPES)
NOT TO SCALE



TYPICAL EVERGREEN PLANTING (ON-SLOPES)
NOT TO SCALE




- EXISTING FEATURES LEGEND**
- EXISTING BUILDING
 - EXISTING CURBING & EDGE OF PAVEMENT
 - EXISTING CONCRETE AREAS
 - EXISTING BITUMINOUS AREAS
 - EXISTING GRAVEL AREAS
 - EXISTING CONTOURS W/ ELEVATION (1'S & 2'S)
 - EXISTING CONTOURS W/ ELEVATION (5'S & 10'S)
 - EXISTING SANITARY SEWER W/ MANHOLE
 - EXISTING WATER LINE W/ VALVE
 - EXISTING STORM SEWER LINE W/ INLET
 - EXISTING GAS LINE
 - EXISTING OVERHEAD UTILITY LINE W/ POLE
 - EXISTING FIRE HYDRANT
 - EXISTING MANHOLE
 - EXISTING UTILITY POLE
 - EXISTING GUY WIRE
 - EXISTING STORM SEWER INLET TYPE-M
 - EXISTING STORM SEWER INLET TYPE-C
 - EXISTING UTILITY MAIN VALVE
 - EXISTING UTILITY METER
 - EXISTING BOLLARD
 - EXISTING CLEAN-OUT
 - EXISTING HANDICAP SYMBOL
 - EXISTING SIGN

- SURVEY FEATURES LEGEND**
- PROPERTY LINE, LOT LINE OR RIGHT OF WAY LINE
 - ADJOINING PROPERTY LINE
 - BUILDING SETBACK LINE
 - EASEMENT LINE
 - PROPERTY CORNER FOUND
 - PROJECT BENCHMARK

- PROPOSED FEATURES LEGEND**
- PROPOSED BUILDING
 - PROPOSED CURBING & EDGE OF PAVEMENT
 - PROPOSED CONCRETE AREAS
 - PROPOSED BITUMINOUS PAVEMENT AREAS
 - PROPOSED RETAINING WALL
 - PROPOSED CHAINLINK FENCE
 - PROPOSED MINOR CONTOURS W/ ELEVATION (1'S & 2'S)
 - PROPOSED MAJOR CONTOURS W/ ELEVATION (5'S & 10'S)
 - PROPOSED 6" PVC SANITARY SEWER LATERAL W/ CLEAN OUT
 - PROPOSED 8" WATER LINE W/ VALVE
 - PROPOSED STORM SEWER W/ TYPE C INLET
 - PROPOSED STORM SEWER ROOF DRAIN
 - PROPOSED STORM SEWER INLET - TYPE M
 - PROPOSED PAINTED HANDICAPPED PARKING SYMBOLS
 - PROPOSED TRAFFIC FLOW ARROWS (NOT PAINTED)

PennTerra ENGINEERING INC.
3075 ENTERPRISE DRIVE
SUITE 100
STATE COLLEGE, PA 16801
PH: 814-231-8285
www.PENNTERRA.com

COPYRIGHT 2024 BY THE ENGINEER
THE INFORMATION CONTAINED HEREIN MAY NOT BE USED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER EXCEPT AS OTHERWISE PROVIDED BY APPROPRIATE LAWS OR STATUTES.
© PENNTERRA ENGINEERING 2024
ALL RIGHTS RESERVED



Designer(s)	MJA
Environmental	MSF
Proj. Manager	CAF
Surveyor	MAX
Perimeter Ck.	
Book	Pg.
File	2226-FINAL-08-LANDSCAPE
Layout	LANDSCAPING PLAN

Date	Description
	REVISIONS

SPACE MART AT VALLEY VISTA

PATTON TOWNSHIP
CENTRE COUNTY
PENNSYLVANIA


PRELIMINARY/FINAL LAND DEVELOPMENT PLAN

LANDSCAPING PLAN

PROJECT NO.
22296


DATE
FEBRUARY 9, 2024

SCALE SHEET NO.
1" = 30' 8



ELECTRICAL NOTES:

- Electrical contractor shall verify and coordinate all existing and new underground facilities with all contractors, utility companies, etc. before beginning any underground construction.
- Wiring under all pavement surfaces shall be in PVC conduit size as indicated - minimum size 1". Electrical contractor shall field verify location of all roadways, walkways, patios, terraces, etc. and provide conduit under all locations for wiring access.
- All circuits shall be complete with ground wire.
- All conduit shall be set at a minimum depth of 24".
- All wiring trenches shall be run as close as possible to all curbs - no wiring shall run through the center of any island, planter, terrace, courtyard, etc. Electrical contractor shall verify conduit location in the field before excavating.
- Contractor shall provide electrical design services and drawings per latest building & electrical code standards for lighting connections, circuitry & controller, and shall be responsible for any code approvals for the design.
- Electrical installation for lighting shall include required wiring and conduit to 5' outside of the building. Building contractor to supply control panels, timing clocks and connection to exterior wiring.
- A 75% reduction in lighting levels shall be maintained during post-curew.



EXISTING FEATURES LEGEND

- Existing Building
- Existing Curbing & Edge of Pavement
- Existing Concrete Areas
- Existing Bituminous Areas
- Existing Gravel Areas
- Existing Contours w/ Elevation (1's & 2's)
- Existing Contours w/ Elevation (5's & 10's)
- Existing Sanitary Sewer w/ Manhole
- Existing Water Line w/ Valve
- Existing Storm Sewer Line w/ Inlet
- Existing Gas Line
- Existing Overhead Utility Line w/ Pole
- Existing Fire Hydrant
- Existing Manhole
- Existing Utility Pole
- Existing Guy Wire
- Existing Storm Sewer Inlet Type-M
- Existing Storm Sewer Inlet Type-C
- Existing Utility Main Valve
- Existing Utility Meter
- Existing Bollard
- Existing Clean-Out
- Existing Handicap Symbol
- Existing Sign
- Existing Soil Limit Line / Boundary
- Existing Soil Type

SURVEY FEATURES LEGEND

- Property Line, Lot Line or Right of Way Line
- Adjoining Property Line
- Building Setback Line
- Easement Line
- Property Corner Found
- Project Benchmark


PROPOSED FEATURES LEGEND

- PROPOSED BUILDING
- PROPOSED CURBING & EDGE OF PAVEMENT
- PROPOSED CONCRETE AREAS
- PROPOSED BITUMINOUS PAVEMENT AREAS
- PROPOSED RETAINING WALL
- PROPOSED CHAINLINK FENCE
- PROPOSED MINOR CONTOURS W/ ELEVATION (1's & 2's)
- PROPOSED MAJOR CONTOURS W/ ELEVATION (5's & 10's)
- PROPOSED 6" PVC SANITARY SEWER LATERAL W/ CLEAN OUT
- PROPOSED 8" WATER LINE W/ VALVE
- PROPOSED STORM SEWER W/ TYPE C INLET
- PROPOSED STORM SEWER ROOF DRAIN
- PROPOSED STORM SEWER INLET - TYPE M
- PROPOSED PAINTED HANDICAPPED PARKING SYMBOLS
- PROPOSED TRAFFIC FLOW ARROWS (NOT PAINTED)

STATISTICS						
DESCRIPTION	SYMBOL	AVG.	MAX.	MIN.	MAX/MIN	AVG/MIN
PAVED AREA	X	2.0 FC	9.0 FC	0.2 FC	45.0:1	10.0:1
TRESPASS	+	0.2 FC	9.0 FC	0.0 FC	N/A	N/A

LUMINAIRE SCHEDULE

SYMBOL	LABEL	QTY.	MANUFACTURER	CATALOG NUMBER	DESCRIPTION	LUMENS PER LAMP	LUMEN MULTIPLIER	LLF	WATTAGE
	A	1	COOPER LIGHTING SOLUTIONS - MCGRAW-EDISON (FORMERLY EATON)	GALN-SA2B-740-U-T4FT-HSS	GALLEON AREA AND ROADWAY LUMINAIRE (2) 70 CRI, 4000K, 800mA LIGHTSQUARES WITH 16 LEDS EACH AND TYPE IV FORWARD THROW OPTICS WITH HOUSE SIDE SHIELD 25' MOUNTING HEIGHT	8228	1	1.00	82.00
	B	3	COOPER LIGHTING SOLUTIONS - MCGRAW-EDISON (FORMERLY EATON)	GALN-SA2B-740-U-T2-HSS	GALLEON AREA AND ROADWAY LUMINAIRE (2) 70 CRI, 4000K, 800mA LIGHTSQUARES WITH 16 LEDS EACH AND TYPE II OPTICS WITH HOUSE SIDE SHIELD 25' MOUNTING HEIGHT	8551	1	1.00	82.00
	C	17	COOPER LIGHTING SOLUTIONS - INVUE (FORMERLY EATON)	CCW-VA-3-740-U-T3	INVUE WALL PACK Wave Stream LUMINAIRE WITH T3 DISTRIBUTION LENS 10' MOUNTING HEIGHT	4516	1	1.00	48.90



PennTerra ENGINEERING INC.
 3075 ENTERPRISE DRIVE
 SUITE 100
 STATE COLLEGE, PA 16801
 PH: 814-231-8285
 www.PENNTERRA.com
 COPYRIGHT 2024 BY THE ENGINEER
 THE INFORMATION CONTAINED HEREIN MAY NOT BE USED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER EXCEPT AS OTHERWISE PROVIDED BY APPROPRIATE LAWS OR STATUTES.
 © PENNTERRA ENGINEERING 2024
 ALL RIGHTS RESERVED

COMMONWEALTH OF PENNSYLVANIA
 REGISTERED PROFESSIONAL ENGINEER
 C. ANTHONY FRUCHTL
 ENGINEER
 PE-062413
 Seal

Designer(s)	MJA
Environmental	MSF
Proj. Manager	CAF
Surveyor	MAX
Perimeter Ck.	
Book	Pg.
File	22296-FINAL-3-LIGHTING PRE
Layout	LIGHTING PLAN PRE CURFEW

Date	Description
	REVISIONS

SPACE MART AT VALLEY VISTA
 PATTON TOWNSHIP
 CENTRE COUNTY
 PENNSYLVANIA

PRELIMINARY/FINAL LAND DEVELOPMENT PLAN


LIGHTING PLAN PRE CURFEW

PROJECT NO.	22296
DATE	FEBRUARY 9, 2024
SCALE	1" = 30'
SHEET NO.	9



ELECTRICAL NOTES:

- Electrical contractor shall verify and coordinate all existing and new underground facilities with all contractors, utility companies, etc. before beginning any underground construction.
- Wiring under all pavement surfaces shall be in PVC conduit size as indicated - minimum size 1". Electrical contractor shall field verify location of all roadways, walkways, patios, terraces, etc. and provide conduit under all locations for wiring access.
- All circuits shall be complete with ground wire.
- All conduit shall be set at a minimum depth of 24".
- All wiring trenches shall be run as close as possible to all curbs - no wiring shall run through the center of any island, planter, terrace, courtyard, etc. Electrical contractor shall verify conduit location in the field before excavating.
- Contractor shall provide electrical design services and drawings per latest building & electrical code standards for lighting connections, circuitry & controller, and shall be responsible for any code approvals for the design.
- Electrical installation for lighting shall include required wiring and conduit to 5' outside of the building. Building contractor to supply control panels, timing clocks and connection to exterior wiring.
- A 75% reduction in lighting levels shall be maintained during post-curew.



EXISTING FEATURES LEGEND

- Existing Building
- Existing Curbing & Edge of Pavement
- Existing Concrete Areas
- Existing Bituminous Areas
- Existing Gravel Areas
- Existing Contours w/ Elevation (1's & 2's)
- Existing Contours w/ Elevation (5's & 10's)
- Existing Sanitary Sewer w/ Manhole
- Existing Water Line w/ Valve
- Existing Storm Sewer Line w/ Inlet
- Existing Gas Line
- Existing Overhead Utility Line w/ Pole
- Existing Fire Hydrant
- Existing Manhole
- Existing Utility Pole
- Existing Guy Wire
- Existing Storm Sewer Inlet Type-M
- Existing Storm Sewer Inlet Type-C
- Existing Utility Main Valve
- Existing Utility Meter
- Existing Bollard
- Existing Clean-Out
- Existing Handicap Symbol
- Existing Sign
- Existing Soil Limit Line / Boundary
- Existing Soil Type

SURVEY FEATURES LEGEND

- Property Line, Lot Line or Right of Way Line
- Adjoining Property Line
- Building Setback Line
- Easement Line
- Property Corner Found
- Project Benchmark

PROPOSED FEATURES LEGEND

- PROPOSED BUILDING
- PROPOSED CURBING & EDGE OF PAVEMENT
- PROPOSED CONCRETE AREAS
- PROPOSED BITUMINOUS PAVEMENT AREAS
- PROPOSED RETAINING WALL
- PROPOSED CHAINLINK FENCE
- PROPOSED MINOR CONTOURS W/ ELEVATION (1's & 2's)
- PROPOSED MAJOR CONTOURS W/ ELEVATION (5's & 10's)
- PROPOSED 6" PVC SANITARY SEWER LATERAL W/ CLEAN OUT
- PROPOSED 8" WATER LINE W/ VALVE
- PROPOSED STORM SEWER W/ TYPE C INLET
- PROPOSED STORM SEWER ROOF DRAIN
- PROPOSED STORM SEWER INLET - TYPE M
- PROPOSED PAINTED HANDICAPPED PARKING SYMBOLS
- PROPOSED TRAFFIC FLOW ARROWS (NOT PAINTED)

STATISTICS						
DESCRIPTION	SYMBOL	AVG.	MAX.	MIN.	MAX/MIN	AVG/MIN
PAVED AREA	X	0.4 FC	2.2 FC	0.0 FC	N/A	N/A
TRESPASS	+	0.0 FC	2.2 FC	0.0 FC	N/A	N/A

LUMINAIRE SCHEDULE

SYMBOL	LABEL	QTY.	MANUFACTURER	CATALOG NUMBER	DESCRIPTION	LUMENS PER LAMP	LUMEN MULTIPLIER	LLF	WATTAGE
⬆	A	1	COOPER LIGHTING SOLUTIONS - MCGRAW-EDISON (FORMERLY EATON)	GALN-SA2B-740-U-T4FT-HSS	GALLEON AREA AND ROADWAY LUMINAIRE (2) 70 CRI, 4000K, 800mA LIGHTSQUARES WITH 16 LEDS EACH AND TYPE IV FORWARD THROW OPTICS WITH HOUSE SIDE SHIELD 25' MOUNTING HEIGHT	8228	1	0.25	82.00
⬆	B	3	COOPER LIGHTING SOLUTIONS - MCGRAW-EDISON (FORMERLY EATON)	GALN-SA2B-740-U-T2-HSS	GALLEON AREA AND ROADWAY LUMINAIRE (2) 70 CRI, 4000K, 800mA LIGHTSQUARES WITH 16 LEDS EACH AND TYPE II OPTICS WITH HOUSE SIDE SHIELD 25' MOUNTING HEIGHT	8551	1	0.25	82.00
⬆	C	17	COOPER LIGHTING SOLUTIONS - INVUE (FORMERLY EATON)	CCW-VA-3-740-U-T3	INVUE WALL PACK Wave Stream LUMINAIRE WITH T3 DISTRIBUTION LENS 10' MOUNTING HEIGHT	4516	1	0.25	48.90

PennTerra ENGINEERING INC.
 3075 ENTERPRISE DRIVE
 SUITE 100
 STATE COLLEGE, PA 16801
 PH: 814-231-8285
 www.PENNTERRA.com
 COPYRIGHT 2024 BY THE ENGINEER
 THE INFORMATION CONTAINED HEREIN MAY NOT BE USED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER EXCEPT AS OTHERWISE PROVIDED BY APPROPRIATE LAWS OR STATUTES.
 © PENNTERRA ENGINEERING 2024
 ALL RIGHTS RESERVED



Designer(s) MJA
 Environmental MSF
 Proj. Manager CAF
 Surveyor MAX
 Perimeter Ck.
 Book Pg.
 File 2226-FINAL-91-LIGHTING POST
 Layout LIGHTING PLAN POST

Date	Description
	REVISIONS


SPACE MART AT VALLEY VISTA
 PATTON TOWNSHIP
 CENTRE COUNTY
 PENNSYLVANIA


PRELIMINARY/FINAL LAND DEVELOPMENT PLAN

LIGHTING PLAN POST CURFEW

PROJECT NO.	DATE
22296	FEBRUARY 9, 2024

SCALE SHEET NO.
 1" = 30'
9.1





SAArchitects		UNIT COUNT MATRIX				
PROJECT No. 22-032	State College North - Green Space Storage	DATE		17-Jan-24		
PHASE 1						
INTERIOR UNITS	1ST FLOOR	2ND FLOOR	3RD FLOOR	SUBTOTAL UNIT COUNT/ SIZE	S/FUNIT	SF TOTAL
(TEMPERATURE CONTROLLED)						
5 x 5	7	5	11	23	25	575
10 x 5	28	42	131	202	50	10,100
10 x 7.5	10	18	38	66	75	3,450
10 x 10	82	148	104	334	100	33,400
10 x 15	39	46	45	130	150	19,500
10 x 20	35	11	11	57	42	2,394
10 x 25	13	0	0	13	250	3,250
10 x 30	14	0	0	14	300	4,200
SUBTOTAL UNIT COUNT/ FLOOR	218	271	320	809		83,875
TOTAL RENTABLE SQUARE FEET						83,875
GROSS BUILDING SQUARE FEET						109,400
PERCENTAGE OF RENTABLE SF						76.6%
AVERAGE UNIT SIZE (SF)						103.7

Designer(s) _____ MJA
 Environmental _____ MSF
 Proj. Manager _____ CAF
 Surveyor _____ MAX
 Perimeter Ck. _____
 Book _____ Pg. _____
 File: 22296-FINAL-10-FLOOR PLANS AND ELEVATIONS
 Layout: FIRST FLOOR

Date _____ Description _____
 REVISIONS

SPACE MART AT VALLEY VISTA

PATTON TOWNSHIP
CENTRE COUNTY
PENNSYLVANIA

**PRELIMINARY/FINAL
LAND DEVELOPMENT
PLAN**

**FIRST FLOOR
PLAN**

PROJECT NO.
22296


DATE
FEBRUARY 9, 2024

SCALE
1/16" = 1'


SHEET NO.
10



1 SOUTH EXTERIOR ELEVATION
SCALE: 1/8" = 1'-0"



2 EAST EXTERIOR ELEVATION
SCALE: 1/8" = 1'-0"



3 WEST EXTERIOR ELEVATION
SCALE: 1/8" = 1'-0"



4 NORTH EXTERIOR ELEVATION
SCALE: 1/8" = 1'-0"

Designer(s)	MJA
Environmental	MSF
Proj. Manager	CAF
Surveyor	MAX
Perimeter Ck.	
Book	Pg.
File	22296-FINAL-10-FLOOR PLANS AND ELEVATIONS
Layout	ELEVATIONS

Date	Description
	REVISIONS


**SPACE MART AT
VALLEY VISTA**

PATTON TOWNSHIP
CENTRE COUNTY
PENNSYLVANIA

**PRELIMINARY/FINAL
LAND DEVELOPMENT
PLAN**


ELEVATIONS

PROJECT NO.	22296
DATE	FEBRUARY 9, 2024
SCALE	N.T.S.
SHEET NO.	13



CEMENT CONCRETE SIDEWALK
NOT TO SCALE


NOTE:
1. CONTROL JOINTS 5' MAX. SPACING, FULL DEPTH EXPANSION JOINTS AT SOLID STRUCTURES, CURB AND BEGINNING AND END OF WORKING DAY.
2. USE SIDEWALK DESIGN SECTION FOR MUNICIPAL CNG FUELING STATION AREA PAD & GATE OPENER PAD.




PAINTED STOP BAR
NOT TO SCALE



CONCRETE BUMPER BLOCK
NOT TO SCALE
P05023



VEHICLE BOLLARD DETAIL
NOT TO SCALE



NOTES:
1. MOUNT SIGN AT RIGHT ANGLE TO DIRECTION OF TRAFFIC FLOW.
2. PROVIDE A MINIMUM CLEARANCE OF ONE FOOT FROM FACE OF CURB.
3. ALL SIGNAGE IS TO BE HIGH INTENSITY REFLECTIVE SHEETING.

SIGN POST DETAIL
NOT TO SCALE




SIGN - S1




SIGN - S2




SIGN - S3




DETECTABLE WARNING SERVICE / RAMP CROSS SECTION
NOT TO SCALE




DEPRESSED CONCRETE CURB
NOT TO SCALE




CONCRETE ISOLATION JOINT
NOT TO SCALE




CONCRETE EXPANSION JOINT DETAIL
NOT TO SCALE




PAVEMENT SECTION PARKING LOT
NOT TO SCALE




6" EXTRUDED STRAIGHT FACE CONCRETE CURB
NOT TO SCALE




CONCRETE CONTROL JOINT
NOT TO SCALE




PAVEMENT NOTCH DETAIL CONNECTION TO LOCAL ROADS
NOT TO SCALE



ALTERNATE TYPE 4A CURB RAMP (PARALLEL)




TYPE 1A CURB RAMP




BIKE RACK DETAIL
NOT TO SCALE


NOTES:
1. BIKE RACK MATERIAL SHALL BE 2" SCHEDULE 40 STEEL.
2. BIKE RACK SHALL BE SURFACE MOUNTED ON CONCRETE.
3. COLOR TO BE DETERMINE BY OWNER.
4. BIKE RACK SHALL HAVE 8 BENDS TO ACCOMMODATE 16 BICYCLES.




HANDICAP PARKING LAYOUT
NOT TO SCALE



PERIMETER CHAINLINK FENCE
NOT TO SCALE



STANDARD PERPENDICULAR CROSSWALK DETAIL
NOT TO SCALE



Designer(s)	MJA
Environmental	MSF
Proj. Manager	CAF
Surveyor	MAX
Perimeter Ck.	
Book	Pg.
File	22296-FINAL-15-DETAILS
Layout	UTILITY DETAILS

Date	Description
	REVISIONS

SPACE MART AT VALLEY VISTA

PATTON TOWNSHIP
CENTRE COUNTY
PENNSYLVANIA


**PRELIMINARY/FINAL
LAND DEVELOPMENT
PLAN**

UTILITY DETAILS

PROJECT NO.
22296

DATE
FEBRUARY 9, 2024


SCALE SHEET NO.
N.T.S. **15**




- LATERAL SPECIFICATIONS:**
- 4" DIAMETER IS THE MINIMUM SIZE. LARGER SIZES WILL BE SPECIFIED BY THE AUTHORITY WHEN THE AMOUNT OF FLOW WARRANTS IT.
 - SLOPE SHALL BE 1/4" PER FOOT UNLESS APPROVED OTHERWISE BY THE AUTHORITY.
 - CLEANOUTS MUST BE INSTALLED EVERY 50' ON 4" PIPE AND EVERY 100' ON 6" PIPE.
 - LATERALS SHALL BE LAID IN AGGREGATE CUSHION AND BEDDING, REFER TO STANDARD PIPE TRENCH DETAIL.
 - CLEANOUT TERMINAL(S) SHALL HAVE TREATMENT AT RESPECTIVE LOCATION. REFER TO DWG. NO.'S 10 & 10A.
 - ALL PIPING MATERIALS INCLUDING TRAPS FOR GRAVITY APPLICATIONS SHALL BE SCHEDULE 40 PVC, ANSI/ASTM D2685.
 - ALL SCHEDULE 40 PVC PIPE USED FOR PRESSURE APPLICATIONS MAY BE STAMPED ASTM D2685 BUT MUST ALSO INCLUDE A SECOND NUMBER, EITHER ASTM D1785 OR ASTM F480, WHICH ARE PRESSURE DESIGNATIONS.

- INSPECTION:**
- WORK MUST BE INSPECTED AND TESTED BEFORE BACKFILLING.
 - THERE IS NO CHARGE FOR ONE-TIME INSPECTION UNLESS THE LATERAL IS LONGER THAN 150' AND/OR IF THE PIPE IS MORE THAN 4" IN DIAMETER.
 - INSPECTIONS REQUIRING MORE THAN ONE VISIT TO THE SITE WILL BE BILLED AT THE RATE IN EFFECT AT THE TIME OF INSPECTION.


TYPICAL SANITARY SEWER LATERAL
NOT TO SCALE




6" SANITARY SEWER CLEAN-OUT DETAIL
NOT TO SCALE




WATER SERVICE TRENCH DETAIL
NOT TO SCALE




NATURAL GAS SERVICE TRENCH DETAIL
NOT TO SCALE



TYPICAL GATE VALVE INSTALLATION
NOT TO SCALE




SANITARY LATERAL TRENCH DETAIL
NOT TO SCALE



ELECTRIC & CABLE TRENCH DETAIL


- NOTES:**
- LIMESTONE SAND BACKFILL PER UTILITY COMPANY STANDARDS.
 - REFER TO UTILITY COMPANY DESIGN PLANS FOR LOCATIONS AND SIZES OF PVC CONDUITS.
 - REDUCE DEPTH OF TRENCH TO 44" FOR SEPARATE SECONDARY TRENCHES FOR ELECTRIC AND COMM (PHONE/CATV) LINES.
 - INSTALL CONDUIT FOR POWER, TELEPHONE, & CATV AS SHOWN ON UTILITY PROVIDER PLANS.
 - PROVIDE 2" MIN. HORIZONTAL CLEARANCE FOR GAS SERVICE WHEN IN COMMON PRIMARY TRENCH. INSTALL GAS SERVICE PER COLUMBIA GAS STANDARD SPECIFICATIONS.



BASIC MATERIALS SCHEDULE		
ITEM	SIZE	DESCRIPTION
1	PLAN	PRECAST CONCRETE METER VAULT (6" WALLS)
2	-	BILCO PCM-4 ALUMINUM HATCH, CAST IN PLACE (MIN. WIDTH 36")
3	-	POLYPROPYLENE ENCASED STEEL STEPS, 12" C TO C
4	8"	FLOOR DRAIN, EITHER CAST OPENING OR GRATED CAST IRON
5	8"x6"	REDUCER
6	6"x6"x6"	MJ TEE
7	6"	GATE VALVE
8	6"	6" DOUBLE CHECK ASSEMBLY, ZURN 350 DA (OR SCBWA APPROVED EQUAL)
9	6"	FLANGED COUPLING ADAPTER
10	6"x1-1/2"	COMPANION FLANGE
11	1-1/2"	BALL VALVE
12	1-1/2"	SENSUS OMNI T ¹ METER
13	1-1/2"	WATTS 007M20T - 1-1/2" DOUBLE CHECK VALVE ASSEMBLY (OR SCBWA APPROVED EQUAL)



- NOTES:**
- PIT MAY BE PRECAST OR BUILT ON SITE WITH CONCRETE BLOCKS WITH PRIOR APPROVAL OF MATERIALS AND METHOD OF CONSTRUCTION BY THE AUTHORITY.
 - HATCH LOCATION MAY BE MOVED WITH AUTHORITY APPROVAL.
 - MEGA-LUGS MUST BE USED ON ALL FITTINGS OR THE FITTINGS MUST BE RODDED (4" MIN.) AND ANCHORED IN CONCRETE IF DUCTILE IRON PIPE IS USED.
 - CONCRETE THRUST BLOCKS MUST BE USED ON ALL UNDERGROUND BENDS AND TEES IF DUCTILE IRON PIPE IS USED.
 - IF 4" PIPE IS USED, METER PIT MUST BE LARGER FOR THE ADDITIONAL FITTING.
 - NO SOLDER JOINTS ALLOWED INSIDE PIT OR UNDERGROUND.
 - METER SETTING INSIDE THE PIPE SHALL CONSIST OF: GATE/BALL VALVE, METER, BACKFLOW PREVENTER, & GATE/BALL VALVE.

METER VAULT FOR 1-1/2" DOMESTIC LINE & 6" FIRE LINE
NOT TO SCALE



- MANUFACTURER NOTES:**
- ALL OF OUR GATES ARE TYPICALLY DRAWN FROM THE PRIVATE SIDE LOOKING OUT.
 - LENGTH AND HEIGHT VARIES. CONSULT WITH AUTOGATE SALES FOR MORE INFORMATION.
 - SHOWN WITH STANDARD S STYLE "E" YOKE. SEE DRAWING #105 FOR YOKE STYLES.
 - CONTOURS AND CURBS WILL REQUIRE CUSTOM DRAWINGS. (CONSULT WITH AUTOGATE).
- NOTES:**
- INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.
 - DO NOT SCALE DRAWING.
 - THIS DRAWING IS INTENDED FOR USE BY ARCHITECTS, ENGINEERS, CONTRACTORS, CONSULTANTS AND DESIGN PROFESSIONALS FOR PLANNING PURPOSES ONLY. THIS DRAWING MAY NOT BE USED FOR CONSTRUCTION.
 - ALL INFORMATION CONTAINED HEREIN WAS CURRENT AT THE TIME OF DEVELOPMENT BUT MUST BE REVIEWED AND APPROVED BY THE PRODUCT MANUFACTURER TO BE CONSIDERED ACCURATE.
 - CONTRACTOR'S NOTE: FOR PRODUCT AND COMPANY INFORMATION VISIT www.CADdetails.com/info AND ENTER REFERENCE NUMBER 22296-FINAL-15-DETAILS

VERTICAL PIVOT GATE SYSTEMS
500 BUCKEYE VERTICAL PIVOT GATE (VPG)



Designer(s)	MJA
Environmental	MSF
Proj. Manager	CAF
Surveyor	MAK
Perimeter Ck.	
Book	Pg.
File	2226-FINAL-PCSM-SI-PLAN
Layout	OVERALL PCSM

Date	Description
	REVISIONS

SPACE MART AT VALLEY VISTA

PATTON TOWNSHIP
CENTRE COUNTY
PENNSYLVANIA


**PRELIMINARY/FINAL
LAND DEVELOPMENT
PLAN**

**POST
CONSTRUCTION
STORMWATER
MANAGEMENT
OVERALL PLAN**

PROJECT NO.
22296

DATE
FEBRUARY 9, 2024

SCALE SHEET NO.
1" = 50' **PC1**



EXISTING FEATURES LEGEND

- Existing Building
- Existing Curbing & Edge of Pavement
- Existing Concrete Areas
- Existing Bituminous Areas
- Existing Gravel Areas
- Existing Contours w/ Elevation (1's & 2's)
- Existing Contours w/ Elevation (5's & 10's)
- Existing Sanitary Sewer w/ Manhole
- Existing Water Line w/ Valve
- Existing Storm Sewer Line w/ Inlet
- Existing Gas Line
- Existing Overhead Utility Line w/ Pole
- Existing Fire Hydrant
- Existing Manhole
- Existing Utility Pole
- Existing Guy Wire
- Existing Storm Sewer Inlet Type-M
- Existing Storm Sewer Inlet Type-C
- Existing Utility Main Valve
- Existing Utility Meter
- Existing Bollard
- Existing Clean-Out
- Existing Handicap Symbol
- Existing Sign
- Existing Soil Limit Line / Boundary
- Existing Soil Type

SURVEY FEATURES LEGEND



- Property Line, Lot Line or Right of Way Line
- Adjoining Property Line
- Building Setback Line
- Easement Line
- Property Corner Found
- Project Benchmark


PROPOSED FEATURES LEGEND

- PROPOSED BUILDING
- PROPOSED CURBING & EDGE OF PAVEMENT
- PROPOSED CONCRETE AREAS
- PROPOSED BITUMINOUS PAVEMENT AREAS
- PROPOSED RETAINING WALL
- PROPOSED CHAINLINK FENCE
- PROPOSED MINOR CONTOURS W/ ELEVATION (1's & 2)
- PROPOSED MAJOR CONTOURS W/ ELEVATION (5's & 1)
- PROPOSED SPOT ELEVATION
- PROPOSED GRADE SLOPE
- PROPOSED 6" PVC SANITARY SEWER LATERAL W/ CLI
- PROPOSED 8" WATER LINE W/ VALVE
- PROPOSED STORM SEWER W/ TYPE C INLET
- PROPOSED STORM SEWER ROOF DRAIN
- PROPOSED STORM SEWER INLET - TYPE M
- PROPOSED PAINTED HANDICAPPED PARKING SYMBOLS
- PROPOSED TRAFFIC FLOW ARROWS (NOT PAINTED)
- NPDES BOUNDARY LINE
- LIMIT OF DISTURBANCE

SOILS LEGEND

Soil cover on the site consists of:
 MrB - Morrison sandy loam, 2%-8% Slopes
 MrC - Morrison sandy loam, 8%-15% Slopes
 URB - Urban land - Hagerstown complex, gently sloping





EXISTING FEATURES LEGEND

- Existing Building
- Existing Curbing & Edge of Pavement
- Existing Concrete Areas
- Existing Bituminous Areas
- Existing Gravel Areas
- Existing Contours w/ Elevation (1's & 2's)
- Existing Contours w/ Elevation (5's & 10's)
- Existing Sanitary Sewer w/ Manhole
- Existing Water Line w/ Valve
- Existing Storm Sewer Line w/ Inlet
- Existing Gas Line
- Existing Overhead Utility Line w/ Pole
- Existing Fire Hydrant
- Existing Manhole
- Existing Utility Pole
- Existing Guy Wire
- Existing Storm Sewer Inlet Type-M
- Existing Storm Sewer Inlet Type-C
- Existing Utility Main Valve
- Existing Utility Meter
- Existing Ballard
- Existing Clean-Out
- Existing Handicap Symbol
- Existing Sign
- Existing Soil Limit Line / Boundary
- Existing Soil Type

SURVEY FEATURES LEGEND

- Property Line, Lot Line or Right of Way Line
- Adjoining Property Line
- Building Setback Line
- Easement Line
- Property Corner Found
- Project Benchmark

PROPOSED FEATURES LEGEND

- PROPOSED BUILDING
- PROPOSED CURBING & EDGE OF PAVEMENT
- PROPOSED CONCRETE AREAS
- PROPOSED BITUMINOUS PAVEMENT AREAS
- PROPOSED RETAINING WALL
- PROPOSED CHAINLINK FENCE
- PROPOSED MINOR CONTOURS W/ ELEVATION (1's & 2)
- PROPOSED MAJOR CONTOURS W/ ELEVATION (5's & 1)
- PROPOSED SPOT ELEVATION
- PROPOSED GRADE SLOPE
- PROPOSED 6" PVC SANITARY SEWER LATERAL W/ CL
- PROPOSED 8" WATER LINE W/ VALVE
- PROPOSED STORM SEWER W/ TYPE C INLET
- PROPOSED STORM SEWER ROOF DRAIN
- PROPOSED STORM SEWER INLET - TYPE M
- PROPOSED PAINTED HANDICAPPED PARKING SYMBOLS
- PROPOSED TRAFFIC FLOW ARROWS (NOT PAINTED)
- NPDES BOUNDARY LINE / LIMIT OF DISTURBANCE

SOILS LEGEND

- Soil cover on the site consists of:
- mB* - Morrison sandy loam, 2%-8% Slopes
 - mC* - Morrison sandy loam, 8%-15% Slopes
 - uRB* - Urban land - Hagerstown complex, gently sloping

PennTerra ENGINEERING INC.
 3075 ENTERPRISE DRIVE
 SUITE 100
 STATE COLLEGE, PA 16801
 PH: 814-231-8285
 www.PENNTERRA.com

COPYRIGHT 2024 BY THE ENGINEER
 THE INFORMATION CONTAINED HEREIN MAY NOT BE USED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER EXCEPT AS OTHERWISE PROVIDED BY APPROPRIATE LAWS OR STATUTES.
 © PENNTERRA ENGINEERING 2024
 ALL RIGHTS RESERVED

COMMONWEALTH OF PENNSYLVANIA
 REGISTERED PROFESSIONAL ENGINEER
 C. ANTHONY FRUCHTL
 ENGINEER PE-062413
 Seal

Designer(s) MJA
 Environmental MSF
 Proj. Manager CAF
 Surveyor MAK
 Perimeter Ck.
 Book Pg.
 File 22296-FINAL-PCSM-02-PLAN
 Layout PCSM PLAN


Date	Description
	REVISIONS

SPACE MART AT VALLEY VISTA
 PATTON TOWNSHIP
 CENTRE COUNTY
 PENNSYLVANIA

PRELIMINARY/FINAL LAND DEVELOPMENT PLAN

POST CONSTRUCTION STORMWATER MANAGEMENT PLAN

PROJECT NO. 22296
 DATE FEBRUARY 9, 2024
 SCALE 1" = 30'
 SHEET NO. **PC2**



P:\pdr\2022\22296\Design\post-construction\final\pcsm-02-plan.dwg, 2/8/2024, 8:40:25 AM, 1:1

STORMWATER MANAGEMENT NOTES:

- 1. All site work shall be done in accordance with the plans prepared by PennTerra Engineering, Inc., the current requirements of the governing municipality, the applicable sections of the PennDOT standard specifications for roadway construction, and all other pertinent federal and state laws.
2. The Contractor shall comply at all times with applicable federal, state and local laws, provisions, and policies governing safety and health, including the federal construction safety act, as amended.
3. The Contractor shall be responsible for examining the areas and conditions under which the project is to be constructed prior to the submission of a bid. Submission of a bid to be constructed to mean the Contractor has reviewed the site and is familiar with conditions and constraints of the site.
4. Before excavation, all underground utilities shall be located in the field by the proper authorities. The Contractor shall notify pa one call 1-800-242-1776. The location of all utilities and underground structures are approximate and may not all be shown. It is the responsibility of the Contractor to determine the existence and exact location of all utilities and underground structures.
5. An as-built drawing of new utility services shall be prepared by the Contractor and submitted to the Owner upon completion of the project.
6. All storm pipe shall be as noted. All joints shall be watertight.
7. Contractor shall refer to other plans within this construction set for other pertinent information.
8. Co-permittee requirements: Contractor to complete Pennsylvania Department of Environmental Protection (D.E.P.) forms and make application to become co-permittee of the individual NPDES permit prior to commencing any land disturbance. Contractor shall assume full responsibility for any fines or other measures assessed by regulatory agencies due to improper or deficient installation and / or maintenance of the temporary erosion and sedimentation control measures and post-construction stormwater measures installed. Contractor shall remain a co-permittee of the National Pollutant Discharge Elimination System (NPDES) permit until the notice of termination of the NPDES permit has been issued by the PA D.E.P.
9. Notice of termination services: Contractor shall be responsible for the services for the notice of termination of the NPDES permit. This includes but is not limited to the following:
a. Have a licensed professional or designee on-site to observe the critical stages of construction noted in the post-construction stormwater management plan. The licensed professional or designee will be responsible for signing the required certification forms and certifying that the facilities have been built according to the approved plans, processing and recording any required forms and the as-built survey through the PA D.E.P. until the notice of termination is received.
b. Prepare an as-built topographic survey sealed by a licensed surveyor from the commonwealth of Pennsylvania of the stormwater management facilities (infiltration basin, rain garden and outlet structures, outlet pipes, tops of berms and spillways)
c. Provide double-ring infiltrometer tests as outlined in the December 2006 PA D.E.P. Stormwater BMP manual of the produced basin bottom soil mix prior to installation to certify that the soil mix meets the infiltration requirements noted on the plans.
10. Contractor shall have a licensed professional submit as-built drawings/documentation (including verification of infiltration testing) of the stormwater management facilities prepared in accordance with the governing municipality's code of ordinances and submitted to the governing municipality at the completion of construction as a prerequisite of issuance of occupancy permit or release of the surety bond. A narrative and photographic documentation for critical stages of construction and for the infiltration surface prior to placement of filter fabric/amended soils must also be submitted to the governing municipality.
11. As-built infiltration testing in infiltration basins shall be performed at the top of the finished native soil layer prior to topsoil placement. This testing is in addition to the testing identified in Note 9.c. The number of infiltration tests performed shall be in accordance with the governing municipality's code of ordinances.

NPDES PERMIT CO-PERMITTEE AND NOTICE OF TERMINATION NOTES:

- 1. The contractor shall process forms with the Local County Conservation District to become a co-permittee on the NPDES. The contractor shall remain a co-permittee until the applicant releases them from the permit.
2. The Notice of Termination requires certification by a licensed professional of the stormwater facilities as noted on the Post Construction Stormwater Management Plan under the section labeled "Critical Stages of Construction".
3. The licensed professional responsible for certifying the Notice of Termination (NOT) of the NPDES permit shall be selected prior to commencing earth disturbance activities on the project site. The general site contractor shall be responsible for supplying & coordinating the licensed professional.
4. The licensed professional responsible for certifying the NOT shall be present for all "Critical Stages of Construction".
5. A pre-construction meeting between the contractor, owner and licensed professional responsible for certifying the NOT is required to ensure all "Critical Stages of Construction" are reviewed, acknowledged and milestones established to ensure the licensed professional is present onsite during the "Critical Stages of Construction."
6. The licensed professional will be required to certify and seal as-built drawings at the end of construction that the stormwater facilities have been built to the specifications on the post construction stormwater management plans and details.
7. Upon completion of all earth moving activities and once site stabilization is achieved in accordance with the Erosion and Sediment Control Plan, the contractor shall then file the as-built drawings and NOT certification with the Local County Conservation District

CRITICAL STAGES OF CONSTRUCTION FOR PROJECTS REQUIRING A GENERAL OR INDIVIDUAL NPDES PERMIT:

Critical Stages of Construction are key components of the construction sequence of the Post Construction Stormwater Management Plan and require certification and construction oversight by the licensed professional responsible for certification of the certified stormwater as-built plan and the NOT.

At least two weeks in advance of construction, the contractor shall schedule a coordination meeting with the licensed professional to review the critical stages and establish a schedule for inspections/verifications of all critical stages. At the discretion of the licensed professional, the contractor will provide photo documentation of the installation of certain items in lieu of the licensed professional being present.

The critical stages for each Post Construction Stormwater Best Management Practice are as follows:

INFILTRATION BASINS

- 1. In order to ensure the basin floor is not compacted, equipment shall not be permitted to operate within the basin when the floor is less than 36" from subgrade elevation. A typical infiltration facility bottom excavation detail has been provided on the plans for construction. The Contractor may develop their own written plan incorporating methods for bottom excavation for review by the municipality and Conservation District. The Contractor must review the proposed methods with the licensed professional, Conservation District and municipality during the Coordination Meeting.
2. Once the subgrade of the facility has been reached, and prior to topsoil placement, the licensed professional and responsible testing firm shall be notified to schedule infiltration testing verification of the subgrade.
3. A typical rock over excavation detail has been provided on the plans. Once the subgrade of the basin floor has been reached, the contractor shall request the licensed professional review the subgrade to determine if rock over excavation is required.
4. Infiltration testing of the final basin floor elevation to verify infiltration rates of the soil mixture (i.e. topsoil and amendments) placed on the basin floor is required. The contractor shall coordinate infiltration testing with the licensed professional and responsible testing firm. It is recommended that this soil mixture also be tested prior to placement.
5. The contractor must notify the licensed professional of the installation of the outlet structure, outfall pipe and anti-seep collars prior to backfill to ensure installation has been completed in accordance with the approved plan.
6. Compaction testing reports are required on the basin berm. The contractor shall coordinate compaction testing with the licensed professional and responsible testing firm.
7. Berms shall be installed and compacted in conformance with the requirements of the local municipality's Stormwater Management Ordinance. If the municipality does not specify compaction requirements, then all berms shall be installed as follows:
a. Whenever berm fill material in excess of 3 feet in height is to be used, each layer of compacted fill shall be tested to determine its density per ASTM D2922 or ASTM D3017.
b. All berm lifts shall be 8" or less.
c. The density of each layer shall be 98% of a Standard Proctor Density analysis per ASTM D698.
8. All proposed vegetation within the limits of construction shall be established to a 70% uniform vegetated cover prior to final notice of termination certification.

NATURALLY OCCURRING GEOLOGIC FORMATIONS/SOIL CONDITIONS:

There are no known naturally occurring geologic formations or soil conditions that pose the potential for pollution during construction. If a sinkhole is encountered due to karst topography, the sinkhole shall be repaired as specified on the sinkhole repair detail and/or a geotechnical engineer must be contacted for proper repair procedures.

GENERAL STORMWATER FACILITY CONSTRUCTION NOTES:

- 1. All site work shall be done in accordance with the plans prepared by PennTerra Engineering, Inc., the current requirements of the governing municipality, the applicable sections of the PennDOT standard specifications for roadway construction, and all other pertinent federal and state laws.
2. The Contractor shall comply at all times with applicable federal, state and local laws, provisions, and policies governing safety and health, including the federal construction safety act, as amended.
3. The Contractor shall be responsible for examining the areas and conditions under which the project is to be constructed prior to the submission of a bid. Submission of a bid to be constructed to mean the Contractor has reviewed the site and is familiar with conditions and constraints of the site.
4. Before excavation, all underground utilities shall be located in the field by the proper authorities. The Contractor shall notify pa one call 1-800-242-1776. The location of all utilities and underground structures are approximate and may not all be shown. It is the responsibility of the Contractor to determine the existence and exact location of all utilities and underground structures.
5. All storm pipes shall be as noted. All joints shall be watertight.
6. Contractor shall refer to other plans within this construction set for other pertinent information.

STORMWATER FACILITY MAINTENANCE NOTES:

All stormwater management facilities on the site of the Spacemart at Valley Vista not contained in a Patton Township Right-of-Way shall be owned and maintained by the developer, Patton Township, its agents and assigns shall have the uninterrupted right to access the property for inspection and maintenance of the stormwater facilities. This note applies to the entire property shown on these plans and shall be in effect for perpetuity.

Patton Township and/or the Centre County Conservation District may require The Owner to maintain a record of all inspections, repairs, and maintenance activities associated with the proposed Stormwater management and permanent erosion and sediment pollution control facilities at this project site. The Owner shall immediately notify Patton Township and Centre County Conservation District prior to initiating any major repair activities.

The Owner hereby acknowledges Patton Township's right to periodically access the project site to inspect the permanent stormwater management facilities that are part of this project. The Owner acknowledges Patton Township's right to access the project site with notice to repair and/or maintain the permanent stormwater management facilities in accordance with this Maintenance Program. Any maintenance and/or repair activities conducted by Patton Township shall be at the expense of the Owner.

The facilities that will require maintenance are the inlets, storm sewer pipes, rip-rap aprons, stormwater basins and swale. All stormwater facilities shall be inspected monthly or after any rainfall events producing 1" of runoff and maintained as follows:

- 1. The proposed storm sewer pipes, inlets and outlets shall be cleaned of all debris, litter, and other deleterious material.
2. The rip-rap apron at the outlet of the pipe need to be inspected to ensure proper erosion protection. If erosion occurs, additional rip-rap should be added.
3. The stormwater infiltration basin shall be cleaned of debris, vegetation maintained to a height of twelve inches, and if any erosion is present the area is to be backfilled with topsoil and seeded with a permanent mixture. The outlet structures shall be kept clean of trash and debris. Vehicular traffic in the basin bottoms shall be limited to the maximum extent possible. The design drain time for the infiltration basins is 72 hours. If standing water persists, contact a registered professional, as the amended topsoil may need re-evaluated for infiltration capacity or be re-lilled and the bottom area re-seeded with the proposed seeding mixture.

RECYCLING AND DISPOSAL OF MATERIALS

THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE, OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1ET SEQ., 271.1 ET SEQ., AND 287.1 ET SEQ. THE CONTRACTOR SHALL NOT ILLEGALLY BURY, DUMP, OR DISCHARGE ANY BUILDING MATERIAL OR WASTES.

WASTES GENERATED DURING THE CONSTRUCTION OF THIS PROJECT SHALL BE RECYCLED IF AT ALL POSSIBLE. ANY MATERIALS THAT CANNOT BE RECYCLED OR REUSED SHALL BE DISPOSED OF AT A PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION APPROVED LANDFILL. IF SOIL AND/OR ROCK DISPOSAL AREAS ARE REQUIRED, EROSION AND SEDIMENTATION CONTROLS SHALL BE IMPLEMENTED AT THESE AREAS. ANY EXCESS SOIL WASTE MAY ONLY BE DISPOSED OF AT AN APPROVED E&S/NPDES PERMITTED SITE.

RESPONSIBILITIES FOR FILL MATERIALS

THE CONTRACTOR IS RESPONSIBLE TO USE ENVIRONMENTAL DUE DILIGENCE TO ENSURE ANY FILL MATERIAL REQUIRED TO BE IMPORTED TO OR EXPORTED FROM THE SITE QUALIFIES AS CLEAN FILL.

CLEAN FILL IS DEFINED AS: UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE.) ENVIRONMENTAL DUE DILIGENCE INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC DATA BASE SEARCHES, REVIEW OF PROPERTY OWNERSHIP, HISTORY, HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS, ANALYTICAL TESTING IS NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF THE PAST LAND USE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE. IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE, IT MUST BE TESTED TO DETERMINE IF IT QUALIFIES AS CLEAN FILL. TESTING SHOULD BE PERFORMED IN ACCORDANCE WITH APPENDIX A OF THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL."

Table with 10 columns: ID, STRUCTURE TYPE, TG ELEV, INVERT IN, INVERT OUT, PIPE RUN, PIPE TYPE, LENGTH (FT), SIZE (IN), SLOPE(%). Rows include OS-1 HDPE END SECTION and 1-1 through 1-5 precast type C modified inlet w/ bicycle safe grate.

Table with 10 columns: ID, STRUCTURE TYPE, TG ELEV, INVERT IN, INVERT OUT, PIPE RUN, PIPE TYPE, LENGTH (FT), SIZE (IN), SLOPE(%). Rows include OS-2 HDPE END SECTION and 1-6 through 1-11 precast type C modified inlet w/ bicycle safe grate.

ALL ROOF DRAINS SHALL BE CONNECTED TO THE STORMSEWER SYSTEM WITH 12" PVC SET AT A MINIMUM OF 0.02% SLOPE AND 2' DEPTH


PennTerra ENGINEERING INC. 3075 ENTERPRISE DRIVE SUITE 100 STATE COLLEGE, PA 16801 PH: 814-231-8285 www.PENNTERRA.com

COPYRIGHT 2024 BY THE ENGINEER

THE INFORMATION CONTAINED HEREIN MAY NOT BE USED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER EXCEPT AS OTHERWISE PROVIDED BY APPROPRIATE LAWS OR STATUTES.

© PENNTERRA ENGINEERING 2024

ALL RIGHTS RESERVED



Blank lines for notes and details.




Date Description REVISIONS

SPACE MART AT VALLEY VISTA PATTON TOWNSHIP CENTRE COUNTY PENNSYLVANIA

PRELIMINARY/FINAL LAND DEVELOPMENT PLAN

POST CONSTRUCTION STORMWATER MANAGEMENT NOTES & DETAILS

PROJECT NO. 22296 DATE FEBRUARY 9, 2024 SCALE N.T.S. SHEET NO. PC3




RIPRAP APRON AT PIPE OUTLET WITHOUT FLARED ENDWALL
NOT TO SCALE

OUTLET NO.	PIPE DIA Pd (N)	RIPRAP		APRON		
		SIZE (R-)	THICK. Rt (N)	LENGTH Al (FT)	INITIAL WIDTH Atw (FT)	TERMINAL WIDTH Atw (FT)
OUT-1	15"	R-3	9"	8.00'	3.75'	11.75'
OUT-2	15"	R-3	9"	8.00'	3.75'	11.75'

- NOTES:
- All aprons shall be constructed to the dimensions shown. Terminal widths shall be adjusted as necessary to match receiving channels.
 - All aprons shall be inspected at least weekly and after each runoff event. Displaced riprap within the apron shall be replaced immediately.
 - Extend riprap on back side of apron to at least 1/2 depth of pipe on both sides to prevent scour around the pipe.

- INFILTRATION BASIN NOTES:**
- THE BASIN SHALL BE INSTALLED PRIOR TO OR CONCURRENT WITH ANY EARTH MOVING OR LAND DISTURBANCE WHICH IT WILL SERVE.
 - THE EMBANKMENT SHALL BE COMPACTED IN LAYERS TO A DENSITY OF 100% MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D698.
 - THE EMBANKMENT SHALL BE CONSTRUCTED WITH SOIL THAT HAS LOW TO MODERATE ERODIBILITY (K FACTOR OF 32 OR LESS).
 - TEMPORARY AND PERMANENT GRASSES OR STABILIZATION MEASURES SHALL BE ESTABLISHED IN THE SIDES AND BASE OF ALL EARTHEN BASINS WITHIN 15 DAYS OF CONSTRUCTION.

INFILTRATION BASIN #1 DETAIL
NOT TO SCALE




STORMWATER MANAGEMENT NOTES:

- All site work shall be done in accordance with the plans prepared by PennTerra Engineering, Inc., the current requirements of the governing municipality, the applicable sections of the PennDOT standard specifications for roadway construction, and all other pertinent federal and state laws.
- The Contractor shall comply at all times with applicable federal, state and local laws, provisions, and policies governing safety and health, including the federal construction safety act, as amended.
- The Contractor shall be responsible for examining the areas and conditions under which the project is to be constructed prior to the submission of a bid. Submission of a bid to be constructed to mean the Contractor has reviewed the site and is familiar with conditions and constraints of the site.
- Before excavation, all underground utilities shall be located in the field by the proper authorities. The Contractor shall notify on a call 1-800-242-1776. The location of all utilities and underground structures are approximate and may not all be shown. It is the responsibility of the Contractor to determine the existence and exact location of all utilities and underground structures.
- An as-built drawing of new utility services shall be prepared by the Contractor and submitted to the Owner upon completion of the project.
- All storm pipes shall be as noted. All joints shall be watertight.
- Contractor shall refer to other plans within this construction set for other pertinent information.
- Co-permittee requirements: Contractor to complete Pennsylvania Department of Environmental Protection (D.E.P.) forms and make application to become co-permittee of the individual NPDES permit prior to commencing any land disturbance. Contractor shall assume full responsibility for any fines or other measures assessed by regulatory agencies due to improper or deficient installation and / or maintenance of the temporary erosion and sedimentation control measures and post-construction stormwater measures installed. Contractor shall remain a co-permittee of the National Pollutant Discharge Elimination System (NPDES) permit until the notice of termination of the NPDES permit has been issued by the PA D.E.P.
- Notice of termination services: Contractor shall be responsible for the services for the notice of termination of the NPDES permit. This includes but is not limited to the following:
 - Have a licensed professional or designee on-site to observe the critical stages of construction noted in the post-construction stormwater management plan. The licensed professional or designee will be responsible for signing the required certification forms and certifying that the facilities have been built according to the approved plans, processing and recording any required forms and the as-built survey through the PA D.E.P. until the notice of termination is received.
 - Prepare an as-built topographic survey sealed by a licensed surveyor from the commonwealth of Pennsylvania of the stormwater management facilities (infiltration basin, rain garden and outlet structures, outlet pipes, tops of berms and spillways).
 - Provide double-ring infiltrometer tests as outlined in the December 2006 PA D.E.P. Stormwater BMP manual of the produced basin bottom soil mix prior to installation to certify that the soil mix meets the infiltration requirements noted on the plans.
- Contractor shall have a licensed professional submit as-built drawings/documentation (including verification of infiltration testing) of the stormwater management facilities prepared in accordance with chapter 147 of the governing municipality's code of ordinances and submitted to the governing municipality at the completion of construction as a prerequisite of issuance of occupancy permit or release of the surety bond. A narrative and photographic documentation for critical stages of construction and for the infiltration surface prior to placement of filter fabric/amended soils must also be submitted to the governing municipality. As-built infiltration testing in infiltration basins shall be performed at the top of the finished native soil layer prior to topsoil placement. This testing is in addition to the testing identified in Note 9.c. The number of infiltration tests performed shall be in accordance with the governing municipality's code of ordinances.

CRITICAL STAGES OF CONSTRUCTION NOTES:

The following stages of construction require that a licensed professional or designee registered within the Commonwealth of Pennsylvania be present onsite. Notice shall be given two weeks prior to commencing construction activities for which the licensed professional will be present. The general site contractor shall be responsible for supplying & coordinating the licensed professional. The licensed professional will be required to certify and seal as-built drawings at the end of construction that the stormwater facilities have been built to the specifications on the post construction stormwater management plans and details. The contractor shall then file this certification with the Centre County Conservation District when the Notice of Termination (NOT) document is completed.

- Installation of proposed Infiltration Basin.



EROSION & SEDIMENTATION CONTROL LEGEND

- NPDES BOUNDARY LINE
- LIMIT OF DISTURBANCE
- CONSTRUCTION ENTRANCE
- INLET PROTECTION
- RIP-RAP APRON
- EROSION CONTROL LINING (CURLEX 1 OR APPROVED EQUAL)
- TOPSOIL STOCKPILE
- TOPSOIL STOCKPILE
- 12" SILT SOCK
- 24" SILT SOCK
- CONCRETE WASHOUT AREA

EXISTING FEATURES LEGEND

- Existing Building
- Existing Curbing & Edge of Pavement
- Existing Concrete Areas
- Existing Bituminous Areas
- Existing Gravel Areas
- Existing Contours w/ Elevation (1's & 2's)
- Existing Contours w/ Elevation (5's & 10's)
- Existing Sanitary Sewer w/ Manhole
- Existing Water Line w/ Valve
- Existing Storm Sewer Line w/ Inlet
- Existing Gas Line
- Existing Overhead Utility Line w/ Pole
- Existing Fire Hydrant
- Existing Manhole
- Existing Utility Pole
- Existing Guy Wire
- Existing Storm Sewer Inlet Type-M
- Existing Storm Sewer Inlet Type-C
- Existing Utility Main Valve
- Existing Utility Meter
- Existing Ballot
- Existing Clean-Out
- Existing Handicap Symbol
- Existing Sign
- Existing Soil Limit Line / Boundary
- Existing Soil Type

SURVEY FEATURES LEGEND

- Property Line, Lot Line or Right of Way Line
- Adjoining Property Line
- Building Setback Line
- Easement Line
- Property Corner Found
- Project Benchmark

PROPOSED FEATURES LEGEND

- PROPOSED BUILDING
- PROPOSED CURBING & EDGE OF PAVEMENT
- PROPOSED CONCRETE AREAS
- PROPOSED BITUMINOUS PAVEMENT AREAS
- PROPOSED RETAINING WALL
- PROPOSED CHAINLINK FENCE
- PROPOSED MINOR CONTOURS W/ ELEVATION (1's & 2's)
- PROPOSED MAJOR CONTOURS W/ ELEVATION (5's & 10's)
- PROPOSED SPOT ELEVATION
- PROPOSED GRADE SLOPE
- PROPOSED 6" PVC SANITARY SEWER LATERAL W/ CLEAN OUT
- PROPOSED 8" WATER LINE W/ VALVE
- PROPOSED STORM SEWER W/ TYPE C INLET
- PROPOSED STORM SEWER ROOF DRAIN
- PROPOSED STORM SEWER INLET - TYPE M
- PROPOSED PAINTED HANDICAPPED PARKING SYMBOLS
- PROPOSED TRAFFIC FLOW ARROWS (NOT PAINTED)



3075 ENTERPRISE DRIVE
SUITE 100
STATE COLLEGE, PA 16801
PH: 814-231-8285

www.PENNTERRA.com

COPYRIGHT 2024 BY THE ENGINEER
THE INFORMATION CONTAINED HEREIN MAY NOT
BE USED OR COPIED IN ANY MANNER WITHOUT
THE WRITTEN PERMISSION OF THE ENGINEER
EXCEPT AS OTHERWISE PROVIDED BY APPROPRIATE
LAWS OR STATUTES.
© PENNTERRA ENGINEERING 2024
ALL RIGHTS RESERVED



Designer(s) MJA
Environmental MSF
Proj. Manager CAF
Surveyor MAX
Perimeter Ck.
Book Pg.
File 22296-FINAL-E&S-01-PLAN
Layout E&S-PC PLAN

Date Description
REVISIONS

DATE DESCRIPTION
REVISIONS

SPACE MART AT VALLEY VISTA

PATTON TOWNSHIP
CENTRE COUNTY
PENNSYLVANIA


PRELIMINARY/FINAL LAND DEVELOPMENT PLAN

EROSION & SEDIMENTATION CONTROL PLAN

PROJECT NO.
22296
DATE
FEBRUARY 9, 2024
SCALE SHEET NO.
1" = 30' ES1



GRAPHIC SCALE



Standard Erosion and Sedimentation Control Plan Notes

- All earth disturbances, including clearing and grubbing as well as cuts and fills shall be done in accordance with the approved E&S plan. A copy of the approved drawings (stamped, signed and dated by the Centre County Conservation District) must be available at the project site at all times. The Centre County Conservation District shall be notified of any changes to the approved plan prior to implementation of those changes. The Centre County Conservation District may require a written submittal of those changes for review and approval at its discretion.
- At least 7 days prior to starting any earth disturbance activities, including clearing and grubbing, the owner and/or operator shall invite all contractors, the landowner, appropriate municipal officials, the E&S plan preparer, the PCSM plan preparer, the licensed professional responsible for oversight of critical stages of implementation of the PCSM plan, and a representative from the Centre County Conservation District to an on-site preconstruction meeting.
- At least 3 days prior to starting any earth disturbance activities, or expanding into an area previously unmarked, the Pennsylvania One Call System Inc. shall be notified at 1-800-242-1776 for the location of existing underground utilities.
- All earth disturbance activities shall proceed in accordance with the sequence provided on the plan drawings. Deviation from that sequence must be approved in writing from the Centre County Conservation District or by the Department prior to implementation.
- Areas to be filled are to be cleared, grubbed, and stripped of topsoil to remove trees, vegetation, roots and other objectionable material.
- Clearing, grubbing, and topsoil stripping shall be limited to those areas described in each stage of the construction sequence. General site clearing, grubbing and topsoil stripping may not commence in any stage or phase of the project until the E&S BMPs specified by the BMP sequence for that stage or phase have been installed and are functioning as described in this E&S plan.
- At no time shall construction vehicles be allowed to enter areas outside the limit of disturbance boundaries shown on the plan maps. These areas must be clearly marked and fenced off before clearing and grubbing operations begin.
- Topsoil required for the establishment of vegetation shall be stockpiled at the location(s) shown on the plan maps(s) in the amount necessary to complete the finish grading of all exposed areas that are to be stabilized by vegetation. Each stockpile shall be protected in the manner shown on the plan drawings. Stockpile heights shall not exceed 35 feet. Stockpile slopes shall be 2H:1V or flatter.
- Immediately upon discovering unforeseen circumstances posing the potential for accelerated erosion and/or sediment pollution, the operator shall implement appropriate best management practices to minimize the potential for erosion and sediment pollution and notify the Centre County Conservation District and/or the regional office of the Department.
- All building materials and wastes shall be removed from the site and recycled or disposed of in accordance with the Department's Solid Waste Management Regulations at 25 Pa. Code 260.1 et seq., 271.1, and 287.1 et seq. No building materials or wastes or unused building materials shall be burned, buried, dumped, or discharge at the site.
- All off-site waste and borrow areas must have an E&S plan approved by the Centre County Conservation District or the Department fully implemented prior to being activated.
- The contractor is responsible for ensuring that any material brought on site is clean fill. Form FP-001 must be retained by the property owner for any fill material affected by a spill or release of a regulated substance by qualifying as clean fill due to analytical testing.
- All pumping of water from any work area shall be done according to the procedure described in this plan, over undisturbed vegetated areas.
- Until the site is stabilized, all erosion and sediment BMPs shall be maintained properly. Maintenance shall include inspections of all erosion and sediment BMPs after each runoff event and on a weekly basis. All preventative and remedial maintenance work, including clean out, repair, replacement, regrading, reseeding, re mulching and renetting must be performed immediately. If the E&S BMPs fail to perform as expected, replacement BMPs, or modifications of those installed will be required.
- A log showing dates that E&S BMPs were inspected as well as any deficiencies found and the date they were corrected shall be maintained on the site and be made available to regulatory agency officials at the time of inspection.
- Sediment tracked onto any public roadway or sidewalk shall be returned to the construction site by the end of each work day and disposed in the manner described in this plan. In no case shall the sediment be washed, shoveled, or swept into any roadside ditch, storm sewer, or surface water.
- All sediment removed from BMPs shall be disposed of in the manner described on the plan drawings.
- Areas which are to be topsoiled shall be scarified to a minimum depth of 3 to 5 inches - 6 to 12 inches on compacted soils - prior to placement of topsoil. Areas to be vegetated shall have a minimum 4 inches of topsoil in place prior to seeding and mulching. Fill outcrops shall have a minimum of 2 inches of topsoil.
- All fills shall be compacted as required to reduce erosion, slippage, settlement, subsidence or other related problems. Fill intended to support buildings, structures and conduits, etc. shall be compacted in accordance with local requirements or codes.
- All earthen fills shall be placed in compacted layers not to exceed 9 inches in thickness.
- Fill materials shall be free of frozen particles, brush, roots, sod, or other foreign or objectionable materials that would interfere with or prevent construction of satisfactory fills.
- Frozen materials or soft, mucky, or highly compressible materials shall not be incorporated into fills.
- Fill shall not be placed on saturated or frozen surfaces.
- Seeps or springs encountered during construction shall be handled in accordance with the standard and specification for subsurface drain or other approved method.
- All graded areas shall be permanently stabilized immediately upon reaching finished grade. Cut slopes in competent bedrock and rock fills need not be vegetated. Seeded areas within 50 feet of a surface water, or as otherwise shown on the plan drawings, shall be blanketed according to the standards of this plan.
- Immediately after earth disturbance activities cease in any area or subarea of the project, the operator shall stabilize all disturbed areas. During non-germinating months, mulch or protective blanketing shall be applied as described in the plan. Areas not at finished grade, which will be reactivated within 1 year, may be stabilized in accordance with the temporary stabilization specifications. Those areas which will not be reactivated within 1 year shall be stabilized in accordance with the permanent stabilization specifications.
- Permanent stabilization is defined as a minimum uniform, perennial 70% vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated erosion. Cut and fill slopes shall be capable of resisting failure due to slumping, sliding, or other movements.
- E&S BMPs shall remain functional as such until all areas tributary to them are permanently stabilized or until they are replaced by another BMP approved by the Centre County Conservation District or the Department.
- Upon completion of all earth disturbance activities and permanent stabilization of all disturbed areas, the owner and/or operator shall contact the Centre County Conservation District for an inspection prior to removal of the E&S BMPs.
- After final site stabilization has been achieved, temporary erosion and sediment BMPs must be removed. Areas disturbed during removal of the BMPs shall be stabilized immediately. In order to ensure rapid revegetation of disturbed areas, such removal are to be done only during the germinating season.
- Upon completion of all earth disturbance activities and permanent stabilization of all disturbed areas, the owner and/or operator shall contact the Centre County Conservation District to schedule a final inspection.
- Failure to correctly install E&S BMPs, failure to prevent sediment-laden runoff from leaving the construction site, or failure to take immediate corrective action to resolve failure of E&S BMPs may result in administrative, civil, and/or criminal penalties being instituted by the Department as defined in Section 602 of the Pennsylvania Clean Streams Law. The Clean Streams Law provides for up to \$10,000 per day in civil penalties, up to \$10,000 in summary criminal penalties, and up to \$25,000 in misdemeanor criminal penalties for each violation.
- Concrete wash water shall be handled in the manner described on the plan drawings. In no case shall it be allowed to enter any surface waters or groundwater systems.
- All channels shall be kept free of obstructions including but not limited to fill, rocks, leaves, woody debris, accumulated sediment, excess vegetation, and construction material/wastes.
- Underground utilities cutting through any active channel shall be immediately backfilled and the channel restored to its original cross-section and protective lining. Any base flow within the channel shall be conveyed past the work area in the manner described in this plan until such restoration is complete.

General Construction Site Notes:

- All permanent and temporary seeding shall be done within 72 hours of the completion of disturbances for all areas requiring vegetative cover.
- Temporary and/or permanent grasses or stabilization shall be established in the sides and base of all earthen basins within 15 days of construction.
- In order to avoid compaction of the proposed infiltration basin bottoms, special procedures shall be implemented as follows:
 - The final excavation shall be completed utilizing equipment located outside the infiltration basin bottom area (if excavation cannot fully be completed from outside the bottoms, refer to the typical infiltration basin bottom excavation detail.)
 - Prior to exiting the site, all construction vehicles must drive over the construction entrance.
 - All disturbed slopes 3:1 and steeper shall be lined with adequate erosion control lining immediately after seeding.
 - Silt Socks must be placed and maintained downslope of all topsoil stockpiles. Topsoil stockpiles must also be seeded with the temporary seeding mixture.
 - All utility installation shall be done at a rate of which all trenching excavated shall be backfilled within the same day. All utility installation shall begin at the very downslope and precede upslope.
 - Each item/step within the sequence of construction must be completed as presented prior to continuing the next step or phase of construction.
 - The contractor is responsible for preparing and implementing any required PPC plans associated with the construction of the site.
 - Failure to correctly install sediment control facilities or failure to prevent sediment laden runoff from leaving the construction site or failure to take corrective actions to immediately resolve failures of sediment control facilities may result in administrative, civil and/or criminal penalties being instituted by the Pennsylvania Department of Environmental Protection as defined in Section 602 of the Clean Streams Law of Pennsylvania. The Clean Streams Law provides for up to \$10,000 per day in civil penalties, up to \$10,000 in summary criminal penalties, and up to \$25,000 in misdemeanor criminal penalties for each violation.

Critical Stages of Construction

- Existing Infiltration Basin. Needs converted to final post construction basin. Remove skimmer, and connect the 6"Perf. PVC underdrain. Once complete installation of the proposed detention basin can occur at this time in accordance with Note-2 above. Installation of the Frebey can occur at this time as well.
- Installation of proposed Infiltration Basin.

Staging of Earthmoving Activities Construction Sequence

- All earth disturbance activities shall proceed in accordance with the following staging of earthmoving activities. Each stage shall be completed before a subsequent stage is initiated.
- Install the proposed rock construction entrance to the site off of the existing gravel access road as shown on the Erosion and Sedimentation Control Plan (E&SOP).
 - Installation of the proposed infiltration basin can occur at this time in accordance with Note 2 above. Installation shall include the outlet structure, outfall pipe, anti-seep collar, and placement of the soil mixture. Stabilize the interior/exterior slopes and top of berm with topsoil, erosion control lining and the permanent seeding mixture. Seed the bottom of the infiltration basin with the infiltration basin bottom permanent seeding mixture. Ensure that the silt sock placed where shown in the basin bottom to protect the bottom of the infiltration basin from sedimentation.
 - Install proposed silt sock as shown on the (E&SOP). Install concrete washout, where shown for use of concrete trucks leaving the site.
 - As construction progresses, stabilize all vegetated areas, with topsoil and the appropriate seeding mixture immediately after they are brought to final grade. Install the appropriate erosion control lining, where shown on the E&SCP. All areas abandoned for more than four (4) days are to be seeded with the temporary seeding mixture.
 - Strip existing topsoil from the site and place the topsoil on the topsoil stockpile as shown on the E&SCP. Place silt sock on the downslope side of the topsoil stockpile as shown on the E&SCP. Seed the topsoil stockpile with the temporary seeding mixture.
 - Begin the rough grading of the remainder of the site.
 - Once final grade of the individual buildings is reached, commence with the building construction. Continue with all parking and driveway construction.
 - Commence with construction of all utilities. All utilities are to be installed at the rate of the length of the utility that can be installed and backfilled in one day. All stormsewer shall be installed beginning at the downstream end and working upstream. Any erosion controls disturbed from the installation of these utilities shall be repaired or replaced properly at the end of each day. Inlet protection shall be placed immediately on all newly installed inlets and outlet protection installed at outlets.
 - Continue with the driveway and parking construction until all utilities are installed. Bring them to sub grade and stabilize with stone.
 - Begin the paving operations, thus removing the rock construction entrance. All curbing and sidewalks shall also be installed.
 - Current regulations state: (a) Upon completion of an earth disturbance activity or any stage or phase of an activity, the site shall be immediately seeded, mulched or otherwise protected from accelerated erosion and sedimentation. (b) Erosion and sediment control BMP's shall be implemented and maintained until the permanent stabilization is completed. (c) For an earth disturbance activity or any stage or phase of an activity to be considered permanently stabilized, the disturbed areas shall be covered with one of the following: (1) A minimum uniform 70% perennial vegetative cover, with a density capable of resisting accelerated erosion and sedimentation. (2) An acceptable BMP which permanently minimizes accelerated erosion and sedimentation. Once stabilization has been achieved, all temporary erosion and sediment controls may be removed as follows:
 - Remove all temporary controls, such as silt sock, topsoil stockpiles, concrete washout and inlet protection. Any areas disturbed by the removal of these controls shall be stabilized immediately with a permanent seeding mixture.

Temporary Control Measures

Temporary control measures will be implemented to ensure that erosion is minimized and that sediment is retained during construction. The rock construction entrance and construction entrance rumble pads (if necessary) will be provided at the site entrance to prevent tracking of sediment from the site. Silt sock will be placed at the locations shown on the Erosion and Sedimentation Control Plan to provide proper filtration of the site runoff. Erosion control lining will be installed to help stabilize the steeper sloped areas to ensure full vegetation is obtained. The topsoil stockpile is provided for a convenient place to stock onsite topsoil. Inlet/yard drain protection and rock filters will be used to prevent sedimentation of the storm sewer systems. Temporary orange construction fence will be used to ensure that sensitive areas are not disturbed.

Temporary seeding on all disturbed areas shall be done immediately after grading is finished and shall consist of the following:	Rate
Item	
1. Agricultural grade limestone	1 ton / acre
2. Fertilizer 10-10-10	500 lbs. / acre
3. Annual ryegrass	40 lbs. / acre
4. Mulch (straw)	3 tons / acre

Permanent Control Measures

Permanent control measures include the stormwater infiltration basin, riprap aprons, swales, storm sewer systems, and seeding / landscaping. Seeding specifications are for graded or cleared areas where permanent vegetative cover is needed.

Soil Enhancements: It is recommended that site specific soil testing be performed. Lieu of soil test recommendations, use the following schedule:

- Acceptable - Apply 6 tons per acre Dolomitic Limestone (240 lbs/ 1000 s.t.) and 1000 lbs/acre 10-20-20 (25 lbs/ 1000 s.t.) before seeding. Harrow or disc into upper three inches of soil.
- Permanent Seeding shall consist of the following:
- | Item | Rate |
|---|---------------|
| 1. Seed Mixture Consisting of | 102 lbs./acre |
| 50% Poa pratensis (Kentucky Bluegrass) | |
| 30% Festuca rubra (Creeping Red Fescue) | |
| 20% Lolium perenne L. (Perennial Rye) | |
| 2. Mulch (straw) | 3 tons / acre |
- Basin Bottom Seeding Mix (To be placed on the bottom and interior sides of the infiltration basin, detention basin, and forebay)
- | Item | Rate |
|---|---------------|
| 1. Seed Mixture Consisting of: | 50 lbs / acre |
| 20% Agrostis alba (Redtop) | |
| 20% Agrostis stolonifera (Creeping Bentgrass) | |
| 20% Elymus riparius (Riverbank Wild Rye) | |
| 20% Carex vulpinoidea (Fox Sedge) | |
| 20% Puccinellia distans (Alkali Grass) | |

- Mulch 3 tons / acre
- Mulching: Apply mulch immediately after seeding and anchor properly with an anchoring tool or following one of the methods listed below.

- Tracking: The process of cutting mulch into the soil via equipment that runs on tracks, is employed primarily on slopes 3:1 or steeper.
- Mulch Nettings: Staple lightweight biodegradable paper, plastic or cotton netting over the mulch according to the manufacturer's recommendations.
- Synthetic Binders: Synthetic binders such as acrylic DLR (AGRI-TAC), DCA-70, Petrosol or TerraLock may be used at rates recommended by the manufacturer to anchor mulch material.
- Wood Cellulose Fiber: The fiber binder shall be applied at a net dry weight of 750 lb/acre. The wood cellulose fiber shall be mixed with water, and the mixture shall contain a maximum of 50 lbs of wood cellulose fiber per 100 gallons.
- Peg & Twine: Drive 8 to 10 inch wooden pegs to within 2 to 3 inches of the soil surface every 4 feet in all directions. Stokes may be driven before or after applying mulch. Secure mulch to surface by stretching twine between pegs in a criss-cross within a square pattern. Secure twine around each peg with two or more turns.

Maintenance Program

During construction, the contractor will be responsible for maintenance and repair of all erosion and sedimentation control facilities. These facilities should be inspected daily and after every runoff event. Any erosion control disturbed during construction, installation of utilities or found to be inadequate upon inspection shall be repaired or replaced within 24 hours after the disturbance or the discrepancy is discovered. The maintenance of the erosion control facilities will include the following:

During inspection of these facilities, written documentation for each inspection for all BMP repair, replacement, and/or maintenance activities shall be completed using the DEP Form 3800-FM-BCW021d (A copy of this form is located in the Appendix of this report). Inspection reports should be kept onsite at all times.

Construction Entrance:

- The entrance shall be maintained in a condition that will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanout of any measure used to trap sediment. All sediment spilled, dropped, washed or tracked onto public rights-of-way must be removed immediately. Sediment removed from the structure shall be spread over an existing stockpile with controls already in place and be seeded with the temporary seeding mixture.

Silt Socks:

- The Contractor shall maintain the socks in a functional condition at all times and it shall be routinely inspected.
- Where the sock requires repair, it will be routinely repaired.
- The contractor shall remove sediment collected at the base of the sock when they reach 1/2 of the exposed height of the sock, or as directed by the Engineer. Alternatively, rather than create a soil disturbing activity, the engineer may call for additional sock to be added at areas of high sedimentation, placed immediately on top of the existing sediment lumen sock. The sock will be dispersed on site when no longer required, as determined by the Engineer.

Topsoil Stockpile/Window:

- The topsoil stockpile shall be seeded with the temporary seeding mixture to ensure proper stabilization. Any additional topsoil spread at these locations shall also be seeded with the temporary seeding mixture.

Permanent Seeding:

- If the vegetative cover is not established uniformly by the third mowing, the contractor shall reapply topsoil if necessary and seed and mulch as needed to provide adequate cover.

Inlet Protection(Bag Type-Installed on Ex F-08):

- Inlet filter bags should be inspected on a weekly basis and after each runoff event. Needed repairs should be initiated immediately after the inspection.
- Filter bags should be cleaned and/or replaced when the bag is 1/2 full. Damaged bags should be replaced.

Inlet Protection (Stone Filter-Installed on I-11 - I-1):

- Sediment shall be removed from the structure and spread over an existing stockpile with controls already in place, and be seeded with the temporary seeding mixture.
- The structure should be checked regularly to ensure its soundness. If the stone filter has been disturbed and cannot perform its proper protective function, additional stone should be installed to provide adequate filtration.

Yard Drain Protection:

- Sediment shall be removed from the structure and spread over an existing stockpile with controls already in place and be seeded with the temporary seeding mixture.
- The structure should be checked regularly to ensure its soundness. If the stone filter has been disturbed and cannot perform its proper protective function, additional stone should be installed to provide adequate filtration.

Concrete Washout Maintenance:

- All concrete washout facilities should be inspected daily.
- Damaged or leaking washouts should be deactivated and repaired or replaced immediately.
- Accumulated materials should be removed when they reach 75% capacity.
- Plastic liners should be replaced with each cleaning of the washout facility.

Spill Materials:

- All sediment removed from erosion and sedimentation pollution control facilities shall be spread over spill areas with controls already in place. Stabilize the spill material with the temporary seeding mixture.

Pumped Water Filter Bag:

- The contractor shall maintain the filter bag in a functional condition at all times and routinely inspect and repair as required.
- Filter bags shall be replaced when they become 1/2 full and spare bags shall be kept available for replacement of failed or filled filter bags.
- The pumping rate shall be observed and be no greater than 750 GPM or 1/2 the maximum specified by the manufacturer, whichever is less.

Recycling and Disposal of Materials

The operator shall remove from the site, recycle, or dispose of all building materials and wastes in accordance with the Department's Solid Waste Management Regulations at 25 Pa. Code 260.1et seq., 271.1 et seq., and 287.1 et seq. The contractor shall not illegally bury, dump, or discharge any building material or wastes.

Wastes generated during the construction of this project shall be recycled if at all possible. Any materials that cannot be recycled or reused shall be disposed of at a Pennsylvania Department of Environmental Protection approved landfill. If soil and/or rock disposal areas are required, erosion and sedimentation controls shall be implemented at these areas. Any excess soil waste may only be disposed of at an approved E&S/NPDES permitted site.

Responsibilities for Fill Materials

The contractor is responsible to use environmental due diligence to ensure any fill material required to be imported to or exported from the site qualifies as Clean Fill.



Clean Fill is defined as: Uncontaminated, non-water soluble, non-decomposable, inert, solid material. The term includes soil, rock, stone, dredged material, used asphalt, and brick, block or concrete from construction and demolition activities that is separate from other waste and is recognizable as such. The term does not include materials placed in or on the waters of the commonwealth unless otherwise authorized. (The term "used asphalt" does not include milled asphalt or asphalt that has been processed for re-use.)

Environmental due diligence: Investigative techniques, including, but not limited to, visual property inspections, electronic data base searches, review of property ownership, review of property use history, Sanborn maps, environmental questionnaires, transaction screens, analytical testing, environmental assessments or audits. Analytical testing is not a required part of due diligence unless visual inspection and/or review of the past land use of the property indicates that the fill may have been subjected to a spill or release of regulated substance. If the fill may have been affected by a spill or release of a regulated substance, it must be tested to determine if it qualifies as clean fill. Testing should be performed in accordance with Appendix A of the Department's policy "Management of Fill".

Fill material that does not qualify as clean fill is regulated fill. Regulated fill is waste and must be managed in accordance with the Department's municipal or residual waste regulations based on 25 Pa. Code Chapters 287 Residual Waste management or 271 Municipal Waste Management, whichever is applicable.



COPYRIGHT 2024 BY THE ENGINEER
THE INFORMATION CONTAINED HEREIN MAY NOT BE USED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER EXCEPT AS OTHERWISE PROVIDED BY APPROPRIATE LAWS OR STATUTES.
© PENNTERRA ENGINEERING 2024
ALL RIGHTS RESERVED



Designer(s)	M.J.A.
Environmental	M.S.F.
Proj. Manager	C.A.F.
Surveyor	M.A.K.
Perimeter Ck.	
Book	Pg.
File	22296-FINAL-E&S-01-NARRATIVE
Layout	E&SCP NARRATIVE

Date	Description
	REVISIONS


SPACE MART AT VALLEY VISTA

PATTON TOWNSHIP
CENTRE COUNTY
PENNSYLVANIA

PRELIMINARY/FINAL LAND DEVELOPMENT PLAN


EROSION & SEDIMENTATION CONTROL NARRATIVE

PROJECT NO.	22296
DATE	FEBRUARY 9, 2024
SCALE	SHEET NO.
N.T.S.	ES2



NOTE: THESE DETAILS REPRESENT TYPICAL SINKHOLE SHAPES AND REPAIR TECHNIQUES. SINKHOLES VARY IN SIZE AND TYPE. THEREFORE, THE OWNER'S GEOTECHNICAL ENGINEER SHALL BE CONTACTED PRIOR TO FIELD REPAIR OF ANY SINKHOLE. (NOT INCLUDED IN UTILITY/EARTHWORK BASE BID)


SINKHOLE REPAIR
 NOT TO SCALE



THIS DETAIL REPRESENTS A TYPICAL INFILTRATION BASIN BOTTOM EXCAVATION TECHNIQUE. EACH INFILTRATION BASIN VARIES WITH GEOMETRY AND OTHER VARIOUS PHYSICAL FEATURES. THE CONTRACTOR MUST DEVELOP A INFILTRATION BASIN BOTTOM EXCAVATION PLAN AND CONSULT WITH THE SITE ENGINEER PRIOR TO COMMENCING THE INFILTRATION BASIN BOTTOM EXCAVATION.

- NOTES:
- ALL EQUIPMENT MOBILIZATION AND MANEUVERS MUST BE LIMITED TO THE TRAVEL PATH LOCATIONS. THE CONTRACTOR SHALL LOCATE AND CLEARLY POST ALL TRAVEL PATHS IN THE FIELD.
 - TRAVEL PATH LOCATIONS SHALL BE SELECTED BASED UPON EQUIPMENT REACH CAPABILITY AND INFILTRATION BASIN GEOMETRY.
 - TRAVEL PATH LOCATIONS SHOULD BE SELECTED SUCH THAT THEY PARALLEL THE LONGEST SIDE OF THE INFILTRATION BASIN.
 - TRAVEL PATH SPACING SHALL VARY WITH EQUIPMENT REACH CAPABILITY. REACH CAPABILITY SHOULD BE A MINIMUM OF 20 FEET.
 - MATERIAL SHALL BE REMOVED FROM THE TRAVEL PATH LOCATIONS WORKING TOWARD THE INFILTRATION BASIN ACCESS POINTS. ONCE MATERIAL IS REMOVED FROM EACH TRAVEL PATH LOCATION AND FINAL GRADE IS ACHIEVED, ALL EQUIPMENT SHALL BE PROHIBITED FROM THESE LOCATIONS.


TYPICAL INFILTRATION BASIN BOTTOM EXCAVATION
 NOT TO SCALE



RIPRAP APRON AT PIPE OUTLET WITHOUT FLARED ENDWALL
 NOT TO SCALE

OUTLET NO.	PIPE DIA Pd (IN)	RIPRAP		APRON		
		SIZE (R-...)	THICK. Rt (IN)	LENGTH (FT)	INITIAL WIDTH Aw (FT)	TERMINAL WIDTH Aw (FT)
OUT-1	15"	R-3	9"	8.00'	3.75'	11.75'
OUT-2	15"	R-3	9"	8.00'	3.75'	11.75'

- NOTES:
- All aprons shall be constructed to the dimensions shown. Terminal widths shall be adjusted as necessary to match receiving channels.
 - All aprons shall be inspected at least weekly and after each runoff event. Displaced riprap within the apron shall be replaced immediately.
 - Extend riprap on back side of apron to at least 1/2 depth of pipe on both sides to prevent scour around the pipe.




Low volume filter bags shall be made from non-woven geotextile material seam with high strength, double stitched "J" type seams. They shall be capable of trapping particles larger than 150 microns. High volume filter bags shall be made from woven geotextiles that meet the following standards:

Property	Test Method	Minimum Standard
Avg. Wide Width Strength	ASTM D-4884	60 lb/in
Grab Tensile	ASTM D-4632	205 lb
Puncture	ASTM D-4833	110 lb
Mullen Burst	ASTM D-3786	350 psi
UV Resistance	ASTM D-4355	70%
AOS % Retained	ASTM D-4751	80 Sieve


- NOTES:
- A suitable means of accessing the bag with machinery required for disposal purposes shall be provided. Filter bags shall be replaced when they become 1/2 full of sediment. Spare bags shall be kept available for replacement of those that have failed or are filled. Bags shall be placed on straps to facilitate removal unless bags come with lifting straps already attached.
 - Bags shall be located in well-vegetated (grassy) area, and discharge onto stable, erosion resistant areas. Where this is not possible, a geotextile underlayment and flow path shall be provided. Bags may be placed on filter stone to increase discharge capacity. Bags shall not be placed on slopes greater than 5%. For slopes exceeding 5%, clean rock or other non-erodible and non-polluting material may be placed under the bag to reduce slope steepness.
 - No downslope sediment barrier is required for most installations. Compost berm or compost filter sock shall be installed below bags located in HQ or EV watersheds, within 50 feet of any receiving surface water or where grassy area is not available.

PUMPED WATER FILTER BAG DETAIL
 NOTE: THIS DETAIL SHALL BE USED FOR PUMPING OF WATER FROM THE SITE
 NOT TO SCALE




- NOTES:
- INSTALL ON FLAT GRADE FOR OPTIMUM PERFORMANCE.
 - CONCRETE WASHOUT MAY BE STACKED IN A PYRAMIDAL CONFIGURATION FOR ADDED HEIGHT AND STABILITY.
 - CONCRETE WASHOUT MAY BE DIRECT SEEDED AT THE TIME OF INSTALLATION.
 - A SUITABLE IMPERVIOUS GEOMEMBRANE SHALL BE PLACED AT THE LOCATION OF THE WASHOUT PRIOR TO INSTALLING THE FILTER SOCKS.

CONCRETE WASHOUT AREA
 NOT TO SCALE




TYPICAL ANCHORING PATTERN (1.1 STAPLES/YD²)

NOTE: THE FOLLOWING STAPLE PATTERN SHALL BE USED FOR ALL EROSION CONTROL LINING INSTALLATION.




- NOTES:
- SEED AND SOIL AMENDMENTS SHALL BE APPLIED ACCORDING TO THE RATES IN THE PLAN DRAWINGS PRIOR TO INSTALLING THE BLANKET.
 - PROVIDE ANCHOR TRENCH AT TOE OF SLOPE IN SIMILAR FASHION AS AT TOP OF SLOPE.
 - SLOPE SURFACE SHALL BE FREE OF ROCKS, CLOUDS, STICKS, AND GRASS.
 - BLANKET SHALL HAVE GOOD CONTINUOUS CONTACT WITH UNDERLYING SOIL THROUGHOUT ENTIRE LENGTH. LAY BLANKET LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH BLANKET.
 - THE BLANKET SHALL BE STAPLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
 - BLANKETED AREAS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70% COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS SHALL BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.


EROSION CONTROL BLANKET INSTALLATION
 NOT TO SCALE



CONSTRUCTION ENTRANCE
 NOT TO SCALE



DROP INLET FILTER W/ EARTHEN BERM (TYPE C)
 NOT TO SCALE



- NOTES:
- SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2.
 - SILT SOCK COMPOST/SOIL/ROCK/SEED FILL TO MEET APPLICATION REQUIREMENTS.
 - SILT SOCKS DESIGNED ARE FOR USE ON MINIMAL SLOPES. GREATER SLOPES MAY REQUIRE LARGER SILT SOCKS PER THE ENGINEER.
 - COMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER.
 - TRAFFIC SHALL NOT BE PERMITTED TO CROSS FILTER SOCKS.
 - ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES HALF THE ABOVEGROUND HEIGHT OF THE SOCK AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN.
 - SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION.
 - ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES HALF THE ABOVEGROUND HEIGHT OF THE SOCK AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN.
 - POLYPROPYLENE SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR.
 - POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
 - UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

TABLE 4.1
 Compost Sock Fabric Minimum Specifications

Material Type	3 mil HDPE	5 mil HDPE	5 mil HDPE	Multi-Filament Polypropylene (MFPF)	Heavy Duty Multi-Filament Polypropylene (HDMFPF)
Material Characteristics	Photo-degradable	Photo-degradable	Bio-degradable	Photo-degradable	Photo-degradable
Sock Diameters	12" 18"	12" 18" 24" 32"	12" 18" 24" 32"	12" 18" 24" 32"	12" 18" 24" 32"
Mesh Opening	3/8"	3/8"	3/8"	3/8"	1/8"
Tensile Strength		26 psi	26 psi	44 psi	202 psi
Ultraviolet Stability % Original Strength (ASTM G-155)	23% at 1000 hr.	23% at 1000 hr.		100% at 1000 hr.	100% at 1000 hr.
Minimum Functional Longevity	6 months	9 months	6 months	1 year	2 years

Two-Ply Systems


Inner Containment Netting	HDPE biaxial net Continuously wound Fusion-welded junctures 3/4"x3/4" Max. aperture size
Outer Filtration Mesh	Composite Polypropylene Fabric (Woven layer and non-woven fleece mechanically fused via needle punch) 3/16" Max. aperture size

Sock fabrics composed of burlap may be used on projects lasting 6 months or less.

TABLE 4.2
 Compost Standards

Organic Matter Content	25%-100% (dry weight basis)
Organic Portion	Fibrous and elongated
pH	5.5-8.5
Moisture Content	30%-60%
Particle Size	30%-50% pass through 3/8" sieve
Soluble Salt Concentration	5.0 dS/m (mmhos/cm) Maximum

COMPOST FILTER SOCK DETAIL
 NOT TO SCALE



INLET FILTER BAG (TYPE C)
 NOT TO SCALE

- INLET FILTER BAG NOTES:
 FILTER BAG SHOULD TRAP PARTICLES LARGER THAN 150 MICRONS. WHEREVER FILTER BAGS ARE USED THEY SHOULD BE INSTALLED ACCORDING TO MANUFACTURER'S SPECIFICATIONS.
 INLET FILTER BAGS SHOULD BE INSPECTED ON A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT.
 FILTER BAGS SHOULD BE CLEANED AND/OR REPLACED WHEN BAG IS 1/2 FULL. DAMAGED FILTER BAGS SHOULD BE REPLACED. NEEDED REPAIRS SHOULD BE INITIATED IMMEDIATELY AFTER THE INSPECTION.